

First Article Test Report.pdf	(FAT Program & TRs) see below list
Structural Analysis Report.pdf	(MCF CEN Equipment)
TP-1073-AR-1.pdf	(Lift Casting Static Load)
TP-1073-AR-002.pdf	(Module Construction Exam)
TP-1073-AR-003.pdf	(Module Lifting Test)
DAAK-73-D0007.pdf	(Structural Analysis Report)
B950201.pdf	(MCF Vibration Testing 1995)
TP-1073-AR-016.pdf	(MCF Vibration Testing 1996)
TP-1073-AR-019.pdf	(MCF Module Compatibility)
TP 1073-AR-042.pdf	(Sea/Beach Module FAT)

Appendix A	Test Report TP-1073-AR-011, Rev. (C), "Centralize Propulsion and Maneuvering Trials"
Appendix B	Test Report TP-1073-AR-012, Rev. (D), "Speed Trials"
Appendix C	Test Report TP-1073-AR-013, Rev. (A), "Fuel Consumption"
Appendix D	Test Report TP-1073-AR-014, Rev. (B), "Ventilation"
Appendix E	Test Report TP-1073-AR-015, Rev. (C), "Noise Level"
Appendix F	Test Report TP-1073-AR-016, Rev. (A), "Vibration Measurements"
Appendix G	Test Report TP-1073-AR-020, Rev. (C), "Emergency Anchor System"
Appendix H	Test Report TP-1073-AR-023, Rev. (A), "Rail Impact Test"

**RETURN TO INDEX**

LAKE SHORE INC.  
An Oldenburg Group Company  
KINGSFORD, MI

SHEET 1 OF 5  
DATE September 28, 1994

TP-1073-AR-003  
CDRL A010

P40 P001  
P20 R003

**MODULE LIFTING TEST  
TEST PROCEDURE**

TP-1073-AR-003

CUSTOMER ATCOM

CUSTOMER JOB NO. N/A

CUSTOMER P.O. NO. DAAK01-93-D-0007

HULL NOS. N/A

EQUIPMENT All Causeway Ferry

EQUIPMENT NO. \_\_\_\_\_

EQUIPMENT SERIAL NO(S) \_\_\_\_\_

CUSTOMER NOTIFICATION PRIOR TO TESTING 2 Weeks

ENGINEERING NOTIFICATION PRIOR TO TESTING None

LAKE SHORE SALES ORDER NO. 1073AR

DRAWN W Keller DATE 9-30-94

CHECKED RMS Shernawski DATE 9-30-94

APPROVED W Keller DATE 9-30-94

QUALITY ASSURANCE R. Dawson DATE 10/3/94

REV.	DATE	APP'D BY	Q.A.	DESCRIPTION
A	OCT 20, 1994	RMS	LSI 1 QA	REVISED TO INCORP NSWC CADEROCK DIV COMMENTS RECEIVED OCT 20, 1994
B	OCT 31, 1994	WJK	LSI 1 QA	REVISED SECTIONS 3, 1, 5 AND 6 TO INCORPORATE COMMENTS OF T. Q. SMARICH LTR 1073-TJC-3938P. ADDED TOLERANCES TO 5, 1 AND NOMENCLATURE TO T.R-003.

LSI 02987

TP-1073-AR-003  
CDRL A010

## MODULE LIFTING TEST TEST PROCEDURE

TP-1073-AR-003

### 1.0 PURPOSE

- 1.1 Purpose of this test is to demonstrate that each module design type meets the requirements of paragraph 4.5.2.1 of Reference 2.1.

### 2.0 REFERENCES

- 2.1 Purchase Description P.D. 1990-0098
- 2.2 ISO 668
- 2.3 ISO 1161
- 2.4 LSI Drawing T-1931, Test Fixture - Lifting Spreader

### 3.0 EQUIPMENT REQUIRED

#### 3.1 CFE.

The following Contractor Furnished Equipment (CFE) is required:

- Lifting spreader bars
  - Two 8' bars minimum capacity 15 tons each
  - One special spreader per Reference 2.4
- Dead weight equal to the weight of:
  - One 20' Module (approximately 11,700#)
  - One 40' Powered Module (approximately 38,600#; plus component dead wts 15,700#)
- One module of each type:
  - One 20' Module
  - One 40' Powered Module

#### 3.2 GFE.       None

### 4.0 INSPECTION CRITERIA

- 4.1 Following testing the modules shall be inspected for the following defects:

TP-1073-AR-003  
CDRL A010

- Any signs of permanent deformation or other abnormalities resulting from lift tests.
- Changes in dimensional requirements affecting module handling, securing or interchange resulting from lift test.

## 5.0 ACCEPTANCE CRITERIA

- 5.1 Any permanent deformation resulting in module dimensional changes greater than ISO 668 and 1161 requirements shall be cause for rejection of the module. Final module dimensions tolerances shall be +0/-3/8 for length, +0/-3/16 width and height.

## 6.0 PROCEDURE

- 6.1 Inspect module per TP-1073-AR-002 noting any irregularities.
- 6.2 On 40' module mark and measure length at top and bottom and two diagonals on each side. On 20' module mark and measure deck length and one diagonal on each side. Measure points should be center-punch located in appropriate area of ISO corner castings.
- 6.3 Apply a uniform load such that the module and test load equal twice the weight of the module. Power module dead weight to include weight of any missing components.
- 6.4 Slowly lift module and hold in air for five minutes while suspended vertically from the four top corner fittings.
- 6.4.1 Inspect module for any permanent deformations resulting from vertical lift test. Record per paragraph 7.0.
- 6.5 Suspend module at 30° ( $\pm 3^\circ$ ) from the four bottom corner fittings, (except raked module and sea/beach module, which are not applicable) using spreader of Reference 2.4 for a period of five minutes.
- 6.6 Inspect module following bottom corner suspension for any permanent deformation resulting from this test. Record measurement per 7.0.

## 7.0 REPORTING

- 7.1 Form TR-1073-AR-003 shall be used for all reporting of results of this test.
- 7.2 All final dimensions shall be recorded and reviewed by customer and LSI engineering.
- 7.3 Customer's representatives presence is required for this test.

TR-1073-AR-003  
CDRL A010

MODULE LIFT TEST  
TEST REPORT

TR-1073-AR-003

CUSTOMER ATCOM

CUSTOMER CONTRACT DAAK01-93-D-0007

EQUIPMENT Causeway Ferry Pontoons

SHOP ORDER \_\_\_\_\_

TEST COMPLETION DATE 1 NOV 94

Record the following for each module:

Acceptable

Not Acceptable

Verify equipment is in current calibration

OK

\_\_\_\_\_

Gauges in current calibration

N/A

\_\_\_\_\_

Tape measure in current calibration

YES

\_\_\_\_\_

Module Serial Number Powered- 40FT P #001

Total Weight of Lift Test 77,031 #

Dimensional check results.

TOP LIFT TEST Top Punch Marks In different locations from Bottom Lift	Dimension Prior To Test	Dimension Post Test	Acceptable	Not Acceptabl e
Length at Top R	38' 10 <sup>3</sup> / <sub>8</sub> "	38' 10 <sup>7</sup> / <sub>16</sub> "	yes	
Length at Bottom R	39' 8 <sup>1</sup> / <sub>2</sub> "	39' 8 <sup>1</sup> / <sub>2</sub> "	yes	
Length at Top L	38' 10 <sup>3</sup> / <sub>16</sub> "	38' 10 <sup>3</sup> / <sub>16</sub> "	yes	
Length at Bottom L	39' 8 <sup>5</sup> / <sub>8</sub> "	39' 8 <sup>5</sup> / <sub>8</sub> "	yes	
Diagonal "A" R (Fwd Top)	39' 5 <sup>5</sup> / <sub>16</sub> "	39' 6"	yes	
Diagonal "B" R (Fwd Bottom)	39' 6"	39' 6"	yes	
Diagonal "A" L (Fwd Top)	39' 6"	39' 6"	yes	
Diagonal "B" L (Fwd Bottom)	39' 5 <sup>7</sup> / <sub>8</sub> "	39' 5 <sup>15</sup> / <sub>16</sub> "	yes	

TR-1073-AR-003  
CDRL A010

BOTTOM LIFT TEST	Dimension Prior To Test	Dimension Post Test	Acceptable	Not Acceptabl e
Length at Top R	39' 8 <sup>7</sup> / <sub>16</sub> "	39' 8 <sup>7</sup> / <sub>16</sub> "	Yes	
Length at Bottom R	39' 8 <sup>3</sup> / <sub>4</sub> "	39' 8 <sup>3</sup> / <sub>4</sub> "	Yes	
Length at Top L	39' 8 <sup>1</sup> / <sub>16</sub> "	39' 8 <sup>1</sup> / <sub>16</sub> "	Yes	
Length at Bottom L	39' 8 <sup>7</sup> / <sub>8</sub> "	39' 8 <sup>15</sup> / <sub>16</sub> "	Yes	
Diagonal "A" R (Fwd Top)	39' 11 <sup>1</sup> / <sub>16</sub> "	39' 11 <sup>1</sup> / <sub>16</sub> "	Yes	
Diagonal "B" R (Fwd Bottom)	39' 11 <sup>5</sup> / <sub>8</sub> "	39' 11 <sup>5</sup> / <sub>8</sub> "	Yes	
Diagonal "A" L (Fwd Top)	39' 11 <sup>5</sup> / <sub>8</sub> "	39' 11 <sup>5</sup> / <sub>8</sub> "	Yes	
*Diagonal "B" L (Fwd Bottom)	39' 11 <sup>1</sup> / <sub>16</sub> "	39' 11 <sup>1</sup> / <sub>2</sub> "	Yes	

20' module s/n P20RR #003		Total Wt. of Lift Test		24,350
NOTES LENGTH TOP L	18' 9 <sup>5</sup> / <sub>16</sub> "	18' 9 <sup>5</sup> / <sub>16</sub> "	Yes	
LENGTH TOP R	18' 9 <sup>1</sup> / <sub>8</sub> "	18' 9 <sup>1</sup> / <sub>8</sub> "	Yes	
DIAGONAL L	19' 1 <sup>3</sup> / <sub>4</sub> "	19' 1 <sup>3</sup> / <sub>4</sub> "	Yes	
DIAGONAL R	19' 1 <sup>1</sup> / <sub>16</sub> "	19' 1 <sup>1</sup> / <sub>16</sub> "	Yes	
END TOP LENGTH	7' 9 <sup>7</sup> / <sub>8</sub> "	7' 9 <sup>7</sup> / <sub>8</sub> "	Yes	
END Bottom Length	7' 9 <sup>15</sup> / <sub>16</sub> "	7' 9 <sup>15</sup> / <sub>16</sub> "	Yes	
Top L - Bottom R Diagonal	8' 11 <sup>9</sup> / <sub>16</sub> "	8' 11 <sup>1</sup> / <sub>2</sub> "	Yes	
Top R - Bottom L Diagonal	8' 11 <sup>1</sup> / <sub>2</sub> "	8' 11 <sup>1</sup> / <sub>2</sub> "	Yes	

Test Witnessed by:

LSI QA Daryl Bailey Customer Rep 1 NOV 94 Other \_\_\_\_\_

LSI Engineering W. H. H. 11/1/94

50 FT. STARRETT TAPE S/N WMQC-003

Calib. Due 7/11/99 Last cal 7/11/94

See 1 SA of 4  
For TRANSVERSE

LSI 02991

# Bottom Lift Test - 40P

5A 055

	<u>Prior</u>	<u>Post</u>	<u>Acceptable</u>
Length Top Forward	7' 9 1/4"	7' 9 5/16"	yes
Length Bottom Forward	7' 9 5/16"	7' 9 5/16"	yes
Top L - Bottom R Diagonal	8' 10 7/8"	8' 10 15/16"	yes
Top R - Bottom L Diagonal	8' 10 9/16"	8' 10 9/16"	yes

---

Length Top AFT	7' 9 7/8"	7' 9 7/8"	yes
Length Bottom AFT	7' 9 7/8"	7' 9 7/8"	yes
Top L - Bottom R. AFT	8' 11 1/16"	8' 11 1/16"	yes
Top R - Bottom Left AFT	8' 11 9/16"	8' 11 1/2"	yes

---

	<u>Top Lift Test - 40P</u>		
	<u>Prior</u>	<u>Post</u>	<u>Acceptable</u>
Length Top Forward	7' 9 5/16"	7' 9 5/16"	yes
Length Bottom Forward	7' 9 5/16"	7' 9 5/16"	yes
Top L - Bottom R Diagonal	8' 10 15/16"	8' 10 15/16"	yes
Top R - Bottom L Diagonal	8' 10 9/16"	8' 10 9/16"	yes

Length Top AFT	7' 9 7/8"	7' 9 7/8"	yes
Length Bottom AFT	7' 9 7/8"	7' 9 7/8"	yes
Top L - Bottom R AFT	8' 11 1/16"	8' 11 1/16"	yes
Top R - Bottom L AFT	8' 11 1/2"	8' 11 1/2"	yes

LAKE SHORE INC.  
An Oldenburg Group Company  
KINGSFORD, MI

SHEET 1 OF 6  
DATE September 28, 1994

TP-1073-AR-004  
CDRL A010

**LONGITUDINAL RESTRAINT  
TEST PROCEDURE**

TP-1073-AR-004

CUSTOMER ATCOM

CUSTOMER JOB NO. N/A

CUSTOMER P.O. NO. DAAK01-93-D-0007

HULL NOS. N/A

EQUIPMENT All Causeway Ferry

EQUIPMENT NO. \_\_\_\_\_

EQUIPMENT SERIAL NO(S) \_\_\_\_\_

CUSTOMER NOTIFICATION PRIOR TO TESTING 2 Weeks

ENGINEERING NOTIFICATION PRIOR TO TESTING None

LAKE SHORE SALES ORDER NO. 1073AR

DRAWN W Keller DATE 9-30-94

CHECKED PM Shingh DATE 9-30-94

APPROVED W Keller DATE 9-30-94

QUALITY ASSURANCE R Mathew DATE 10/3/94

REV.	DATE	APP'D BY	Q.A.	DESCRIPTION
A	10/3/94	WJK	LSI 1 QA	REVISED SECTIONS 3, 1, 5 AND 6 TO INCORPORATE COMMENTS OF TCSA LETTER OF 10/27/94 S/N 1073-NC- 3938P. CHANGED TEST LOAD TO 80K IN LIEU OF 2X MODULUS IN IP 6.0 CLARIFIED ACCEPTANCE PROCEEDURE IN P.5.0.

LSI 03089



TP-1073-AR-004  
CDRL A010

## LONGITUDINAL RESTRAINT TEST PROCEDURE

TP-1073-AR-004

### 1.0 PURPOSE

- 1.1 Purpose of this test is to demonstrate that each module design type meets the longitudinal restraint requirements of paragraph 4.5.2.2 of Reference 2.1.

### 2.0 REFERENCES

- 2.1 Purchase Description P.D. 1990-0098
- 2.2 ISO 668
- 2.3 ISO 1161
- 2.4 LSI Drawing T-1932, Longitudinal Restraint Test Fixture

### 3.0 EQUIPMENT REQUIRED

#### 3.1 CFE.

The following Contractor Furnished Equipment (CFE) is required:

- Module restraining and test fixture per Reference 2.4.
- Hydraulic cylinder, 50 ton capacity, Model RC-506 or equal, effective area of pistons 11.045 sq./in.
- HPU with current calibration.
- One 40' Module

*NOTE: Test cannot be performed on sea/beach or raked modules.*

#### 3.2 GFE.

None

TP-1073-AR-004  
CDRL A010

#### 4.0 INSPECTION CRITERIA

4.1 Following testing the modules shall be inspected for the following defects resulting from restraint test.

- Any signs of permanent deformation or other abnormalities.
- Changes in dimensional requirements affecting module handling, securing or interchange.

#### 5.0 ACCEPTANCE CRITERIA

5.1 Any permanent deformation resulting in module dimensional tolerance change greater than the following final dimensions shall be cause for rejection of the module:

5.1.1 +0/-3/8 Length

5.1.2 +0/-3/16 height and width.

#### 6.0 PROCEDURE

6.1 Prior to testing inspect module per TP-1073-AR-002. Note any existing deformations.

6.2 Measure and mark diagonal and length dimensions prior to applying loads.

6.2.1 Weight of module + machinery is 38,600#.

6.2.2 Test Module to 80,000# to allow for machinery foundations.

6.3 Pressure on cylinder for pushing and pulling is obtained from the following equation:  
*NOTE: This rest requires two cylinders.*

$$P = F/A$$

$$P = \text{Pressure on Cylinder}$$

$$F = \text{Force for Test (80,000\#)}$$

$$A = \text{Area of one Cylinder} = 11.045 \text{ in.}^2$$

$$A_T = \text{Area of two cylinders} = 22.09 \text{ in.}^2$$

Thus,

$$P = (80,000\#)/22.09 \text{ in.}^2 = 3622 \text{ PSIG}$$

LSI 03091

TP-1073-AR-004  
CDRL A010

6.4 Restrain module at one end using bottom corner fittings.

6.4.1 Apply a horizontal load of 80,000# through the opposite bottom corner fittings, first towards then away from the restrained fittings.

6.2.2 Hold load five minutes in each direction.

6.5 Following each load application measure and record diagonal and length dimensions.

6.6 Perform on one P40 module only.

## 7.0 REPORTING

7.1 Form TR-1073-AR-004 shall be used for all reporting of results of this test.

7.2 All final dimensions shall be recorded and reviewed by customer and LSI engineering.

7.3 Customer representative is required to witness this test.

PRESSURE GAGE	S/N 880998	CAL. DUE 10-28-95	LAST CAL 10-28-95
PRESSURE GAGE	S/N 880999	CAL. DUE 10-28-95	LAST CAL 10-28-95
PRESSURE GAGE	S/N 880996	CAL DUE 10-28-95	LAST CAL 10-28-95
STARRETT 50' TAPE	S/N 881121	CAL DUE 10-28-95	LAST CAL 10-28-95
BRIDGE AMP	S/N 884008	CAL DUE 7-29-95	LAST CAL 7-29-95
BRIDGE AMP	S/N 884001	CAL DUE 7-1-95	LAST CAL 7-1-95
STOP WATCH	S/N 881043	CAL DUE 10-28-95	LAST CAL 10-28-95

TR-1073-AR-004  
CDRL A010

# LONGITUDINAL RESTRAINT

## TEST REPORT

TR-1073-AR-004

CUSTOMER ATCOM

CUSTOMER CONTRACT DAAK01-93-D-0007

EQUIPMENT Causeway Ferry Pontoons

SHOP ORDER \_\_\_\_\_

TEST COMPLETION DATE 2 Nov 94

Record the following for each module tested:

Acceptable

Not Acceptable

Gauges in current calibration

YES

Tape in current calibration

YES

Verify cylinder area of 11.045 in.<sup>2</sup>

YES

Module Serial Number P40 #001

Total Load Applied 80,000#

Dimensional check results (see Reference 2.2, 2.3)

COMPRESSION TEST TENSION	Dimension Prior To Test	Dimension Post, Test	Acceptable	Not Acceptable
Length at Top R	38' 11 11/16"	38' 11 5/8"	YES	
Length at Bottom R	38' 11 3/8"	38' 11 3/8"	YES	
Length at Top L	38' 11 9/16"	38' 11 1/2"	YES	
Length at Bottom L	38' 11 1/4"	38' 11 3/16"	YES	
Diagonal "A" R	39' 2"	39' 2"	YES	
Diagonal "B" R	39' 1 7/8"	39' 1 7/8"	YES	
Diagonal "A" L	39' 1 7/8"	39' 1 7/8"	YES	
Diagonal "B" L	39' 1 5/8"	39' 1 9/16"	YES	

LSI 03093

TR-1073-AR-004  
CDRL A010

<del>TENSION TEST</del> COMPRESSION	Dimension Prior To Test	Dimension Post Test	Acceptable	Not Acceptable
Length at Top R	38' 11 <sup>5</sup> / <sub>8</sub> "	38' 11 <sup>1</sup> / <sub>16</sub> "	yes	
Length at Bottom R	38' 11 <sup>3</sup> / <sub>8</sub> "	38' 11 <sup>3</sup> / <sub>8</sub> "	yes	
Length at Top L	38' 11 <sup>1</sup> / <sub>2</sub> "	38' 11 <sup>1</sup> / <sub>2</sub> "	yes	
Length at Bottom L	38' 11 <sup>1</sup> / <sub>4</sub> "	38' 11 <sup>3</sup> / <sub>16</sub> "	yes	
<sup>PWD TOP</sup> Diagonal "A" R	39' 1 <sup>3</sup> / <sub>4</sub> "	39' 2"	yes	
Diagonal "B" R	39' 2"	39' 1 <sup>7</sup> / <sub>8</sub> "	yes	
<sup>PWD TOP</sup> Diagonal "A" L	39' 1 <sup>7</sup> / <sub>8</sub> "	39' 1 <sup>7</sup> / <sub>8</sub> "	yes	
Diagonal "B" L	39' 1 <sup>3</sup> / <sub>4</sub> "	39' 1 <sup>9</sup> / <sub>16</sub> "	yes	

NOTES \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Test Witnessed by:

LSI Rep Nancy Poirier 11-02-94 Customer Rep Donald H. Poirier 11-02-94 Other \_\_\_\_\_  
LSI Engineering Rep W. J. Miller 11-2-94

LSI 03094

LAKE SHORE INC.  
An Oldenburg Group Company  
KINGSFORD, MI

SHEET 1 OF 6  
DATE September 28, 1994

TP-1073-AR-005  
CDRL A010

**MODULE RIGIDITY TEST  
TEST PROCEDURE**

TP-1073-AR-005

CUSTOMER ATCOM

CUSTOMER JOB NO. N/A

CUSTOMER P.O. NO. DAAK01-93-D-0007

HULL NOS. N/A

EQUIPMENT All Causeway Ferry

EQUIPMENT NO. N/A

EQUIPMENT SERIAL NO(S) N/A

CUSTOMER NOTIFICATION PRIOR TO TESTING 2 WEEKS

ENGINEERING NOTIFICATION PRIOR TO TESTING None

LAKE SHORE SALES ORDER NO. 1073AR

DRAWN W Keller DATE 9-30-94

CHECKED R.M. Sherman DATE 9-30-94

APPROVED W Keller DATE 9-30-94

QUALITY ASSURANCE R. Mattson DATE 10/3/94

REV.	DATE	APP'D BY	Q.A.	DESCRIPTION
A	OCT 31, 1994	WJK	LSI 1 QA	Revised TP 5 TO CLARIFY ACCEPTANCE CRITERIA Revised TP 6.4 AND 6.6 TO CLARIFY TEST MEASUREMENTS. MODIFIED TR- 005 TO CLARIFY DIAGONAL MEASUREMENTS.

LSI 03095

TP-1073-AR-005  
CDRL A010

**TEST PLAN  
MODULE RIGIDITY TEST**

**TP-1073-AR-005**

**1.0 PURPOSE**

- 1.1 Purpose of this test is to demonstrate that each module design type meets the requirements to withstand ship racking forces of paragraph 4.5.2.3 of Reference 2.1.

**2.0 REFERENCES**

- 2.1 Purchase Description P.D. 1990-0098
- 2.2 ISO 668
- 2.3 ISO 1161
- 2.4 ISO 1496/1
- 2.5 LSI Drawing T-1933, Test Fixture Module Racking Test

**3.0 EQUIPMENT REQUIRED**

**3.1 CFE.**

The following Contractor Furnished Equipment (CFE) is required:

- Module restraining and test fixture per Reference 2.5.
- Hydraulic cylinder, 50 ton capacity, Model RC-506 or equal, effective area of pistons 11.045 sq./in.
- Hydraulic Power Unit with gauges in current calibration.
- One 40' Powered Module

**3.2 GFE.**

None

TP-1073-AR-005  
CDRL A010

#### 4.0 INSPECTION CRITERIA

4.1 Following testing the modules shall be inspected for the following defects resulting from this test:

- Any signs of permanent deformation or other abnormalities.
- Changes in dimensional requirements affecting module handling, securing or interchange.

#### 5.0 ACCEPTANCE CRITERIA

##### 5.1 End Structure

The sideways deflection of the top of the module with respect to the bottom of the module at the time it is under full transverse rigidity test conditions, shall not cause the sum of the changes in length of the two diagonals to exceed 2 3/8".

##### 5.2 Side Structure

The longitudinal deflection of the module with respect to the bottom of the module at the time it is under full longitudinal rigidity test conditions, shall not exceed 1".

#### 6.0 PROCEDURE

6.1 Inspect modules for completion per procedure TP-1073-AR-002. Note any existing deformations or non-conformities.

6.2 Punch mark locations on side and end to be tested and measure ISO to ISO diagonal reference dimensions. Measure two diagonals per side and end. Record per Section 7.0 of this procedure.

##### 6.3 Traversed Rigidity Test.

The module shall be placed on four level supports, one under each corner fitting, and shall be restrained against lateral and vertical movement by means of anchor devices acting through the bottom apertures of the bottom corner fittings. Lateral restraint shall be provided only at a bottom corner fitting diagonally opposite to the top corner fitting to which force is applied. Vertical restraint shall be applied only at the end frame under test.



TP-1073-AR-005  
CDRL A010

A force of 33,000 lbs. shall be applied to the top corner fitting in a line parallel both to the base and to the plane of the end of the module. The force shall be applied first towards and then away from the top corner fittings.

$$P = F/A \quad \therefore P = \frac{33,000}{11.045} = 2988 \text{ psi}$$

Only one end shall be tested.

- 6.4 With transverse racking loads, applied reinspect measured diagonals and record dimensions.

6.5 Longitudinal Rigidity Test.

The module shall be placed on four level supports, one under each corner fitting, and shall be restrained against longitudinal and vertical movement by means of anchor devices acting through the bottom apertures of the bottom corner fittings. Longitudinal restraint shall be provided only at the bottom corner fitting diagonally opposite to and in the same side as the top corner fitting to which force is applied.

Forces of 16,850 lbs. shall be applied to the top corner fitting on one end of the module a line parallel both to the base of the module and to the plane of the sides of the module. The force shall be applied first towards and then away from the top corner fitting.

$$P = F/A \quad \therefore P = \frac{16,850}{11.045} = 1526 \text{ psi}$$

Only one side shall be tested.

- 6.6 With longitudinal racking loads applied, reinspect measured diagonals and record dimensions.

- 6.7 Longitudinal test cannot be applied to the raked modules or to the beach/sea module.

7.0 REPORTING

- 7.1 Form TR-1073-AR-005 shall be used for all reporting of results of this test.

- 7.2 All final dimensions shall be recorded and reviewed by customer and LSI engineering.

- 7.3 Customer representation is required to witness this test.

LSI 03098

TRANSVERSE RESULTS  
ON REVERSE →

TR-1073-AR-005  
CDRL A010

MODULE RIGIDITY TEST

TEST REPORT

TR-1073-AR-005

CUSTOMER ATCOM

CUSTOMER CONTRACT DAAK01-93-D-0007

EQUIPMENT Causeway Ferry Pontoons

SHOP ORDER \_\_\_\_\_

TEST COMPLETION DATE 2 NOV 94

	<u>Acceptable</u>	<u>Not Acceptable</u>
Module is inspected per paragraph 6.1.	<u>yes</u>	_____
Test set-up is per reference 2.5.	<u>yes</u>	_____
Gauges are in current calibration.	<u>yes</u>	_____
Verify cylinder area of 11.045 in. <sup>2</sup>	<u>yes</u>	_____

Record the following for each module:

Module Serial Number P40P # 001

Dimensional check results (see Reference 2.2, 2.3, 2.4)

<u>TRAVERSE TEST</u>	<u>Acceptable</u>	<u>Not Acceptable</u>
----------------------	-------------------	-----------------------

NOTE: Diagonal "A" is defined as top corner at point of load.

Diagonal "A" - Before Test	<u>8' 11"</u>	
<i>Push</i> Diagonal "A" - During Test	<u>8' 10 <sup>15</sup>/<sub>16</sub>"</u>	<u>yes</u>
Diagonal "B" - Before Test	<u>8' 10 <sup>5</sup>/<sub>8</sub>"</u>	
Diagonal "B" - During Test	<u>8' 10 <sup>5</sup>/<sub>8</sub>"</u>	<u>yes</u>
Diagonal "A" - After Test	<u>8' 10 <sup>15</sup>/<sub>16</sub>"</u>	
Diagonal "B" - After Test	<u>8' 10 <sup>9</sup>/<sub>16</sub>"</u>	

LSI 03100

LAKE SHORE INC.  
An Oldenburg Group Company  
KINGSFORD, MI

SHEET 6 OF 6  
DATE September 28, 1994  
REVISED October 31, 1994

TR-1073-AR-005  
CDRL A010

Total Load Applied 33,000 lbs at pressure of 3000 PSI.

LONGITUDINAL TEST

Acceptable

Not Acceptable

NOTE: Diagonal "A" defined as top corner at point of load.

	PUSH	PULL	
Diagonal "A" - Before Test	39' 11 9/16"	39' 11 9/16"	
Diagonal "A" - During Test	39' 11 9/16"	39' 11 9/16"	yes
Diagonal "B" - Before Test	39' 6 1/8"	39' 6 1/8"	
Diagonal "B" - During Test	39' 6 1/8"	39' 6 1/8"	yes

Total Load Applied 17,672 at pressure of 1600 PSI.

Test Witnessed by:

LSI Rep Nancy Perier 11/02/94 Customer Rep Donald K. Bailey Other Willie J. Johnson 11/2/94  
LSI 526.

Pressure Gage	S/N 880998	Cal. Due 10-28-95	Last Cal. 10-28-94
Pressure Gage	S/N 880999	Cal. Due 10-28-95	Last Cal. 10-28-94
Pressure Gage	S/N 880996	Cal. Due 10-28-95	Last Cal. 10-28-94
Starrett 50' Tape	S/N 881121	Cal. Due 10-28-95	Last Cal. 10-28-94
Bridge Amp.	S/N 884008	Cal. Due 7-29-95	Last Cal. 7-29-94

LSI 03101

LAKE SHORE INC.  
An Oldenburg Group Company  
KINGSFORD, MI

SHEET 1 OF 4  
DATE September 28, 1994

TP-1073-AR-006  
CDRL A010

MODULE STACKING TEST  
TEST PROCEDURE

720 CR004

TP-1073-AR-006

CUSTOMER ATCOM

CUSTOMER JOB NO. N/A

CUSTOMER P.O. NO. DAAK01-93-D-0007

HULL NOS. N/A

EQUIPMENT All Causeway Ferry

EQUIPMENT NO. N/A

EQUIPMENT SERIAL NO(S) N/A

CUSTOMER NOTIFICATION PRIOR TO TESTING 2 Weeks

ENGINEERING NOTIFICATION PRIOR TO TESTING None

LAKE SHORE SALES ORDER NO. 1073AR

DRAWN W. Keller DATE 9.30.94

CHECKED R.M. Sheparshi DATE 9-30-94

APPROVED W. Keller DATE 9.30.94

QUALITY ASSURANCE R. Mattson DATE 10/3/94

REV.	DATE	APP'D BY	Q.A.	DESCRIPTION
A	OCT 31, 1994	WSK	LSI 1 QA	Revised #6 AND TR-006 TO REFLECT ONLY ONE CORNER IS TO BE TESTED IN LIEU OF ALL FOUR.

LSI 03102

TP-1073-AR-006  
CDRL A010

## MODULE STACKING TEST TEST PROCEDURE

TP-1073-AR-006

### 1.0 PURPOSE

- 1.1 Purpose of this test is to demonstrate that each module design type meets the stacking requirements of paragraph 4.5.2.4 of Reference 2.1.

### 2.0 REFERENCES

- 2.1 Purchase Description P.D. 1990-0098
- 2.2 ISO 668
- 2.3 ISO 1161
- 2.4 LSI Drawing T-1929, Fixture for Stack and Deck Strength

### 3.0 EQUIPMENT REQUIRED

#### 3.1 CFE.

The following Contractor Furnished Equipment (CFE) is required:

- Restraining and test load fixture per Reference 2.4.
- Hydraulic cylinder, 50 ton capacity, Model RC-506 or equal, effective area of pistons 11.045 sq./in.
- HPU with gauges in current calibration.
- One module randomly selected from first article production.

#### 3.2 GFE.

None

### 4.0 INSPECTION CRITERIA

- 4.1 Following testing the module shall be inspected for the following defects:

- Any signs of permanent deformation or other abnormalities.
- Changes in dimensional requirements affecting module handling, securing or interchange.

LSI 03103

TP-1073-AR-006  
CDRL A010

## 5.0 ACCEPTANCE CRITERIA

- 5.1 Any permanent deformation resulting in module dimensions no longer meeting the requirements of references 2.2 and 2.3 shall be cause for rejection of the module.

## 6.0 PROCEDURE

- 6.1 NOTE: All LSI MCF modules have identical corner scantlings making testing of each type redundant test only one randomly selected module.

- 6.2 Inspect module per test plan TP-1073-AR-002 prior to this test. Note any existing deformations.

- 6.3 Mark a known dimension on one vertical corner fitting pair (approximately 4'-3") and center punch.

- 6.4 Apply a compressive load of 86,800# to one corner fitting of the module. *4 ft*

$$P = F/A \quad \therefore P = 86,800/11.045 = 7.859 \text{ psi}$$

*USE  $P = 101,520 \text{ #}$ ,  $P = 9042 \text{ psi}$*

- 6.5 Hold load for 5 minutes.

- 6.6 Inspect corner fitting to fitting dimension.

- 6.7 NOTE: 86,800# is 1/4 the weight of 15-1/2 40' modules stacked vertically. (Total height of 69'-9" on top of bottom most module. *SEE TR-006 NOTES FOR REVISION*)

## 7.0 REPORTING

- 7.1 Form TR-1073-AR-006 shall be used for all reporting of results of this test.

- 7.2 All final dimensions shall be recorded and reviewed by customer and LSI engineering.

- 7.3 Customer representative is required to witness this test.

Pressure Gauge	S/N	880988	Due 10-28-95	Last Cal. 10-28-94
Pressure Gauge	S/N	880999	Due 10-28-95	Last Cal. 10-28-94
50 FT. Starrett Tape	S/N	WMQC-003	Due 7-11-99	Last Cal. 7-11-94
Pressure Gauge	S/N	880996	Due 10-28-95	Last Cal. 10-28-94

LAKE SHORE INC.  
An Oldenburg Group Company  
KINGSFORD, MI

SHEET 4 OF 4  
DATE September 28, 1994

TR-1073-AR-006  
CDRL A010

## MODULE STACKING TEST

### TEST REPORT

TR-1073-AR-006

CUSTOMER ATCOM

CUSTOMER CONTRACT DAAK01-93-D-0007

EQUIPMENT Causeway Ferry Pontoons

SHOP ORDER \_\_\_\_\_

TEST COMPLETION DATE 1 NOV 94

Record the following for each module:      Acceptable      Not Acceptable

Equipment is in current calibration.      yes      \_\_\_\_\_

Verify cylinder area of 11.045 in.<sup>2</sup>      yes      \_\_\_\_\_

Module Serial Number P20CR #004

Total Load Applied 9200 PSIG

Dimensional check results (see Reference 2.2, 2.3) and paragraph 6.3.

	Before	After	
	Rear Side	Rear Side	
Corner 1	<u>52" 51"</u>	<u>52" 51"</u>	Acceptable <u>yes</u> Not Acceptable _____

Notes TEST WEIGHT CHANGED TO 5 NEW PONTON + 3 PONTON ISOPIES

OR  $[(36,000 + 23,260) \times 3 + (22,400 + 23,260) \times 5] \div 4 = 101,520 / \text{area} = 9192 \text{ PSIG}$

Test Witnessed by:

LSI Rep Daryl Baily 11-1-94 Customer Rep \_\_\_\_\_ Other \_\_\_\_\_

LSI Engineering Rep W. Miller 11/1/94

LSI 03105

LAKE SHORE INC.  
An Oldenburg Group Company  
KINGSFORD, MI

SHEET 1 OF 5  
DATE September 28, 1994

TP-1073-AR-007  
CDRL A010

**MODULE FITTINGS TEST  
TEST PROCEDURE**

TP-1073-AR-007

CUSTOMER ATCOM

CUSTOMER JOB NO. N/A

CUSTOMER P.O. NO. DAAK01-93-D-0007

HULL NOS. N/A

EQUIPMENT All Causeway Ferry

EQUIPMENT NO. \_\_\_\_\_

EQUIPMENT SERIAL NO(S) \_\_\_\_\_

CUSTOMER NOTIFICATION PRIOR TO TESTING 2 Weeks

ENGINEERING NOTIFICATION PRIOR TO TESTING None

LAKE SHORE SALES ORDER NO. 1073AR

DRAWN W/Keller DATE 9-30-94

CHECKED R M Shemersh DATE 9-30-94

APPROVED W H Kelly DATE 9-30-94

QUALITY ASSURANCE R Mattson DATE 10/3/94

REV.	DATE	APP'D BY	Q.A.	DESCRIPTION
A	OCT. 20, 1994	RMS	LSI 1 QA	REVISED TO INCORP NSW CADEROCK DIV. COMMENTS RECEIVED OCT. 20, 1994
B	OCT 31, 1994	W J K	LSI 1 QA	ADDED # 6.2.6 AND 6.3.6 TO REFLECT TEST METHOD. ADDED REQUIREMENTS FOR MAC PARTICLE TESTING

LSI 03106



TP-1073-AR-007  
CDRL A010

**TEST PLAN  
MODULE FITTINGS TEST**

**TP-1073-AR-007**

**1.0 PURPOSE**

- 1.1 Purpose of this test is to demonstrate that each module deck cleat and tie down fitting design type meets the fitting test requirements of paragraph 4.5.2.5 of Reference 2.1.

**2.0 REFERENCES**

- 2.1 Purchase Description P.D. 1990-0098

**3.0 EQUIPMENT REQUIRED**

**3.1 CFE.**

The following Contractor Furnished Equipment (CFE) is required:

- Module restraint and pull test fixtures.
- One 20' Module
- Iron River Pull Test Facility
- Magnetic Particle Test Equipment

**3.2 GFE.**

None

**4.0 INSPECTION CRITERIA**

- 4.1 Following testing the fittings shall be inspected for the following defects:

- Any signs of permanent deformation or other abnormalities.
- Changes in dimensional requirements affecting fitting installation, securing or interchange.

**5.0 ACCEPTANCE CRITERIA**

- 5.1 Any permanent deformation resulting inability of the fitting to be removed and/or reinstalled shall be cause for rejection of the fittings.

TP-1073-AR-007  
CDRL A010

## 6.0 PROCEDURE

6.1 Verify current calibration of test equipment.

### 6.2 Cargo Tiedown Pull Test

6.2.1 Place module with cargo tiedown in test area and secure.

6.2.1.1 Check welds by magnetic particle method

6.2.2 Test load 30,000# tensile pull.  $30,000 \# / 11.015 = 2717 \text{ PSIG}$  FOR THIS TEST.

6.2.3 Load sequentially around the fitting at 45° intervals in a horizontal plane (8 pulls).

6.2.4 Load at 45° above and below a horizontal plane normal to the side shell plane (2 pulls).

6.2.5 Apply loads for 10 minutes at each location.

6.2.6 Relocate fittings as required to allow for all pull angles.

6.2.7 Following all pull tests recheck welds by magnetic particle method.

### 6.3 Deck Cleat Pull Test

6.3.1 With module secure in test area, install one deck cleat fitting.

6.3.1.1 Check welds by magnetic particle method

6.3.2 Test load 30,000# tensile pull.

6.3.3 Load sequentially around the fitting at 45° intervals in a horizontal plane (8 pulls).

6.3.4 Load at 45° above and below a horizontal plane normal to the side shell plane (2 pulls).

6.3.5 Apply loads for 10 minutes at each location.

6.3.6 Relocate fittings as required to allow for all pull angles.

6.3.7 Following all pull tests recheck welds by magnetic particle method.

LAKE SHORE INC.  
An Oldenburg Group Company  
KINGSFORD, MI

SHEET 4 OF 7  
DATE September 28, 1994  
REVISED October 31, 1994

TP-1073-AR-007  
CDRL A010

## 7.0 REPORTING

7.1 Form TR-1073-AR-007 shall be used for all reporting of results of this test.

7.2 Customer representative is required to witness this test.

	<u>CALDUE</u>	<u>LAST CAL</u>
BRIDGE Amp S/N 884008	7-29-95	7-29-94
Stop Watch S/N 881043	10-28-95	10-28-94

TR-1073-AR-007  
CDRL A010

MODULE FITTINGS TEST

TEST REPORT

TR-1073-AR-007

CUSTOMER ATCOM

CUSTOMER CONTRACT DAAK01-93-D-0007

EQUIPMENT Causeway Ferry Pontoons

PONTOON SERIAL NO. P20L #001

SHOP ORDER \_\_\_\_\_

TEST COMPLETION DATE 3 Nov 94

Record the following for each fitting:                      Acceptable                      Not Acceptable

Calibration of equipment is current.                      YES                      \_\_\_\_\_

Deck cleat loading

<u>Horizontal Pull</u>	<u>Load Applied</u>	<u>Time</u>	<u>Deck Cleat Removable</u>
			<u>Acc</u> <u>Not Acc</u>
Magnetic Particle Inspection			<u>YES</u> _____

#1 Pull 1	<u>30,000 #</u>	<u>10 min.</u>	<u>YES</u>	_____
#3 Pull 2	<u>30,000 #</u>	<u>10 min.</u>	<u>YES</u>	_____
#8 Pull 3	<u>30,000 #</u>	<u>10 min.</u>	<u>YES</u>	_____
#10 Pull 4	<u>30,000 #</u>	<u>10 min.</u>	<u>YES</u>	_____
#12 Pull 5	<u>30,000 #</u>	<u>10 min.</u>	<u>YES</u>	_____
#14 Pull 6	<u>30,000 #</u>	<u>10 min.</u>	<u>YES</u>	_____
#17 Pull 7	<u>30,000 #</u>	<u>10 min.</u>	<u>YES</u>	_____
#19 Pull 8	<u>30,000 #</u>	<u>10 min.</u>	<u>YES</u>	_____

TR-1073-AR-007  
CDRL A010

	<u>Load Applied</u>	<u>Time</u>	<u>Tiedown fitting</u>	<u>Removable</u>
			<u>Acc</u>	<u>Not Acc</u>
#6 45° Above Horz (Normal to side)	<u>30,000 #</u>	<u>10 min</u>	<u>YES</u>	_____
#7 45° Below Horz (Normal to side)	<u>30,000 #</u>	<u>10 min</u>	<u>YES</u>	_____
Magnetic Particle Inspection			<u>YES</u>	_____
Tie down fitting loading				
<u>Horizontal Pull</u>	<u>Load Applied</u>	<u>Time</u>	<u>Tiedown fitting</u>	<u>Removable</u>
			<u>Acc</u>	<u>Not Acc</u>
Magnetic Particle Inspection			<u>YES</u>	_____
#2 Pull 1	<u>30,000 #</u>	<u>10 min.</u>	<u>YES</u>	_____
#4 Pull 2	<u>30,000 #</u>	<u>10 min.</u>	<u>YES</u>	_____
#9 Pull 3	<u>30,000 #</u>	<u>10 min.</u>	<u>YES</u>	_____
#11 Pull 4	<u>30,000 #</u>	<u>10 min.</u>	<u>YES</u>	_____
#13 Pull 5	<u>30,000 #</u>	<u>10 min</u>	<u>YES</u>	_____
#15 Pull 6	<u>30,000 #</u>	<u>10 min.</u>	<u>YES</u>	_____
#16 Pull 7	<u>30,000 #</u>	<u>10 min.</u>	<u>YES</u>	_____
#18 Pull 8	<u>30,000 #</u>	<u>10 min.</u>	<u>YES</u>	_____
#5 45° Above Horz *	<u>30,000 #</u>	<u>10 min.</u>	<u>YES</u>	_____
#21 (Normal to side) <del>Retest</del>	<u>30,000 #</u>	<u>10 min</u>	<u>YES</u>	_____
#20 45° Below Horz	<u>30,000 #</u>	<u>10 min</u>	<u>YES</u>	_____
(Normal to side)				
Magnetic Particle Inspection			<u>YES</u>	_____

LSI 03111

\* Rope Clamp interference with sheave during applied load - Retest.

LAKE SHORE INC.  
An Oldenburg Group Company  
KINGSFORD, MI

SHEET 7 OF 7  
DATE September 28, 1994  
REVISED October 31, 1994

TR-1073-AR-007  
CDRL A010

Notes \_\_\_\_\_

Test Witnessed by:

LSI Rep Nancy Power 11-03-94 Customer Rep Donald N. B. [Signature] Other \_\_\_\_\_  
LSI Engineering Rep [Signature] 11-3-94

LSI 03112

TP-1073-AR-008  
CDRL A010

**MODULAR CAUSEWAY FERRY  
ASSEMBLY LIFTING  
TEST PROCEDURE**

TP-1073-AR-008

CUSTOMER ATCOM

CUSTOMER JOB NO. N/A

CUSTOMER P.O. NO. DAAK01-93-D0007

HULL NOS. First Article

EQUIPMENT Spreader Assembly

EQUIPMENT NO. E19883

EQUIPMENT SERIAL NOS. \_\_\_\_\_

CUSTOMER NOTIFICATION PRIOR TO TESTING 7 DAYS

ENGINEERING NOTIFICATION PRIOR TO TESTING 14 DAYS

LAKE SHORE SALES ORDER NO. 1073AR

DRAWN J.C. L. Zell DATE OCT 14, 1994

CHECKED Rick Sheranski DATE OCT 18 1994

APPROVED William J. Keller DATE OCT 19, 1994

QUALITY Keith Mattson DATE 10/19/94

SHEET 2 OF 9  
DATE October 14, 1994

Rev	Date	Appvl	Q. A.	Description
--	10/21/94	WJK	LSI 1 QA	Initial Issue
A	1/13/95	WJK	LSI 1 QA	Revised entire procedure to reflect new test method
B	1/17/95	WJK	LSI 1 QA	Revised TP and to change from dye penetrant testing

LSI 02994



TP-1073-AR-008  
CDRL A010

**MODULAR CAUSEWAY FERRY  
ASSEMBLY LIFTING  
TEST PROCEDURE**

TP-1073-AR-008

**1.0 INTRODUCTION**

- 1.1 Objective. The objective of the Assembly Lifting Test is to verify the ability of the spreader bar, slings, shackles, and lifting rings have sufficient capacity and safety factor to lift the Modular Causeway Ferry (MCF) Powered Section without deformation or failure. Testing shall demonstrate that the Lifting Assembly will lift a design load of 2.3 times the weight of the Powered Section (2.3 x rated static load).
- 1.2 Test Item. The test item, described as the Spreader Assembly is defined by Lake Shore drawing E19883.
- 1.3 Test Limitations. Assembly Lifting Tests will be conducted on the individual parts of the Spreader Assembly in lieu of testing the completed assembly. Lifting Rings and shackles (integral parts of the module) are tested in accordance with Lake Shore test procedure TP-1073-AR-001; shackles and assembled slings will be certified to the specified load by the manufacture; the spreader bar will be tested at a Lake Shore test facility as specified herein.

**2.0 REFERENCE DOCUMENTS**

- 2.1 PD 1990-0098 Purchase Description (Para's 4.5.2.6, 3.5.25)
- 2.2 Mil-Std-209H Slings and Tiedown Provisions for Lifting and Tying Down Military Equipment
- 2.3 E20001 General Test Requirements
- 2.4 E20011 Failure Reporting, Analysis, and Corrective Action System (FRACAS)
- 2.5 E19983 Instrumentation, Assembly Lifting Test

TP-1073-AR-008  
CDRL A010

### 3.0 TEST PREPARATION

- 3.1 Approach to Test. Assembly Lifting Tests will be conducted on the individual parts of the Spreader Assembly in lieu of testing the completed assembly. Lifting Rings and shackles (integral parts of the module) are tested in accordance with Lake Shore test procedure TP-1073-AR-001; shackles and assembled slings will be certified to the specified load by the manufacture.

The spreader bar is rated at 100 ton lift capacity. To verify the strength of the lifting eyes, each eye will be individually tested to its rating; the crane hook eye (top of beam) will be tested to 2.3 x 100 ton, the two sling hook eyes (bottom of beam) will be tested to 2.3 x 50 ton. The strength of the beam in bending will be verified by calculation.

- 3.2 General Test Requirements. Refer to the following documents for general test requirements:

E20001 General Test Requirements; location and schedule of test, calibration requirements, safety requirements, and general test documentation.

E20011 Failure Reporting, Analysis, and Corrective Action System (FRACAS).

- 3.3 Government Notification. ATCOM and Government Quality Assurance Representative shall be provided with seven (7) days notification prior to the start of testing.

- 3.4 Personnel Requirements. The following personnel are required for performance of the Assembly Lifting Test:

3.4.1 Contractor furnished personnel: Test supervisor, test equipment technicians.

3.4.2 Government furnished personnel: None.

- 3.5 Facilities and Test Equipment. The following facilities, support equipment, and test equipment are required for performance of the Assembly Lifting Test (CFE = Contractor furnished equipment, GFE = Government/Customer furnished equipment):

	<u>CFE</u>	<u>GFE</u>
3.5.1 One (1) Spreader Assembly, E19883;	X	
3.5.2 Instrumentation and load application fixtures, E19983;	X	

- 3.6 The instrumentation for applying and measuring spreader bar loads shall be installed as documented in Lake Shore drawing E19983.

TP-1073-AR-008  
CDRL A010

#### 4.0 TEST PROCEDURE

4.1 Clean welds as indicated on sketch 4.0-1 "NDT Inspection, Proof Test" for dye penetrant inspection.

Ⓟ 4.2 Perform magnetic particle inspection of weld areas indicated in Sketch 4.0-1 prior to testing.

4.3 Assemble test set-up for crane eye test per Reference 2.4.

4.4 Slowly apply pressure to cylinders until load of 230 short tons is applied.

4.4.1 A 230 ton load is based on the following formula:

$$\text{Cylinder Area} \times \text{Pressure} = \text{Load}$$

For Enerpac CLL 1506 Cylinders this becomes:

$$2 \text{ ea} \times 30.69 \text{ in.}^2 \times P = 460,000\#$$

or

$$P = 460,000/2 \times 30.69$$

thus

$$P = 7494 \text{ PSI}$$

4.4.2 APPLY NO MORE THAN 8250 PSI !

4.5 Hold applied load 90 seconds.

4.6 Following removal of load visually inspect all welds and beam for deformation or cracks.

4.7 Rig beams per Reference 2.4 for sling hook eye pull.

4.8 Apply the 7494 psi load per 4.4.1 above.

4.8.1 DO NOT EXCEED 8250 PSI !

4.9 Hold the load for 90 seconds.

TP-1073-AR-008  
CDRL A010

4.10 Following release of load visually inspect the beam and all welds for deformation or cracks.

Ⓟ 4.11 Perform magnetic particle inspections of specific welds per Figure 4.0-1 following all pull test load applications.

## 5.0 ACCEPTANCE CRITERIA.

Acceptance criteria for the Assembly Lift Test is as follows:

5.1 All purchased lift items have proper certification.

5.2 The spreader bar, hook eyes and pads show no signs of permanent deflection or weld failure.

## 6.0 REPORTING

Report data on Form TR-1073-AR-008.

## 7.0 MARKING OF BEAM

Following successful proof loading of each beam stamp the following on the top flange of the beam.


7.1 Date of proof load, "P.L. MO/DAY/YEAR"


7.2 Serial Number of Beam, "E19883 SN X"

7.2.1 X is consecutively numbered starting at 1.

TP-1073-AR-008  
CDRL A010

FIGURE 4.0-1 NDT INSPECTION PROOF TEST B






NOTES:  
1. CENTER SPACERS AND HYD. CYLINDERS DIRECTLY OVER BEAM WEB.

	QTY	CAGE CODE	PART OR IDENT NO	NOMENCLATURE	DESCRIPTION	MATERIAL	WT ZONE
3	2	-	E21982	-	SPACER,27.0"	STL	-
2	2	-	E21972	-	SPACER,45.5"	STL	-
1	2	-	E19872	-	WELDMENT,SPREADER	STL	-

## PARTS LIST

UNLESS OTHERWISE SPECIFIED, ALL DIMENSIONS ARE IN INCHES.		DRAWN		DWR	95/01/16	 <b>LAKE SHORE INC.</b> AN OLERUMETUM COMPANY FROM WILMINGTON, DE 19801
TOLERANCES ARE:		CHECK		CLB	95/01/16	
XXX ± .03		APP		RMS	95/01/17	
XXX ± .015						TITLE
XXX ± .010						MCF LIFT BEAM LOAD TEST
INTERPRET DRAWING IN ACCORDANCE WITH STANDARDS AS DESCRIBED IN DOD-D-1008						DATE OF TEST
E09282						C. 34/12
NEXT ASSY						TIME AND
APPLICATION						E19983

TR-1073-AR-08  
CDRL A010

MODULAR CAUSEWAY FERRY  
ASSEMBLY LIFTING TEST  
TEST REPORT

TR-1073-AR-008

CUSTOMER ATCOM

CUSTOMER P.O. NO. DAAK01-93-D-0007

EQUIPMENT LIFTING ASSEMBLY - E19883

EQUIPMENT SER NO. E19883 S/N 001, 002

SHOP ORDER \_\_\_\_\_

TEST COMPLETION DATE 20 JAN 95

TEST DATA

- Test performed at LSI IRON RIVER Facility.

Acceptable      Not Acceptable

- Visual inspection of welds and beam (use "NOTES" below to report discrepancies.

✓      \_\_\_\_\_

- ② • Magnetic particle of specified welds (use "NOTES" below to report discrepancies).

✓      \_\_\_\_\_

- Hydraulic unit gauges in current calibration.

✓      \_\_\_\_\_

- #880998 CAL 10-28-94  
DUE 10-28-95  
Test assembly is rigged correctly for crane eye test.

✓      \_\_\_\_\_

- Test Load applied to crane eye correctly.

PSI 7500  
Load 460,000 #

✓      \_\_\_\_\_  
✓      \_\_\_\_\_

- 8250 PSI not exceeded.

✓      \_\_\_\_\_

STOP WATCH ~~#881044 CAL DUE 9-14-95 M.~~

#881043 CAL DUE 10-28-95

TR-1073-AR-08  
CDRL A010

	<u>Acceptable</u>	<u>Not Acceptable</u>
• Visual examination results (use "NOTES" below to report discrepancies).	<u>✓</u>	<u>      </u>
• Test assembly is rigged correctly for sling eye test.	<u>✓</u>	<u>      </u>
• Sling eye test load is applied correctly. PSI <u>7500</u> Load <u>460,000</u> #	<u>✓</u> <u>✓</u>	<u>      </u> <u>      </u>
• 8250 PSI not exceeded.	<u>✓</u>	<u>      </u>
• Visual examination results (use "NOTES" below to report discrepancies).	<u>✓</u>	<u>      </u>
② • Magnetic particle check results (use "NOTES" below to report discrepancies).	<u>✓</u>	<u>      </u>
• Unit(s) is (are) correctly stamped.	<u>✓</u>	<u>      </u>
• Vendor data for purchased lift items is correct and complete. <u>Bridle Sling</u>	<u>✓</u>	<u>      </u>

NOTES (Vendor Shackles proof load tested as part of  
the test - Shackles used for testing<sup>only</sup> were  
not used as a "shipped item" <sup>NP</sup>).

Test Witnessed by:

LSI Rep Nancy Poirer Customer Rep Donald R. Beach Other



TR-1073-AR-008  
PRE-TEST INSPECTION  
MAGNETIC PARTICLE INSPECTION REPORT  
OPERATION 20

Lake Shore Inc. Date 11/20/95  
Job No. ARV096 Lift Beam Load Test  
Customer's P.O. No. DAAK01-93-D0007  
Drawing No. E19983 (SPREADER WELDMENT #E19872)  
Serial No. N/A Heat lot Number N/A  
(E001 + E002)  
TO BE STAMPED

1. Magnetic Particle Specification or Procedure No. QAP 17.5  
2. Magnetic Particle Method Wet X Dry  
3. Surface Preparation Machined X Rough  
4. Equipment Portable Prods Stationary Equipment X Yoke  
5. Date Equipment Calibrated 11/2/95  
6. Bath Strength 1.2 to 2.4 ML (Visible) 0.1 to 7 ML (fluorescent)  
7. Magnetic Field X Longitudinal Circular  
8. Apply Particles X Continuous Residual  
9. Determining Amperage for longitudinal 6 AMP AC Yoke

For Circular \_\_\_\_\_

10. Product Spacing 2"-8" Acceptance Standard 2"-8"  
11. Interpretation NO RECORDABLE INDICATIONS FOUND

12. Accepted 2  
Rejected 0  
Tested 2

Inspector Richard M. [Signature]  
Level PT  
Date of Recertification 9/96

TR-1073-AR-008

# Post-test Inspection

MAGNETIC PARTICLE INSPECTION REPORT

Operation 40

Lake Shore Inc.

Date 1/20/95

Job No. ARV096 Lift Beam Load Test

Customer's P.O. No. DAAK01-93-D0007

Drawing No. E19983 (spreader weldment E19872)

Serial No. N/A Heat lot Number N/A

E19883-S/N001

E19883-S/N002

1. Magnetic Particle Specification or Procedure No. QAP 17.5

2. Magnetic Particle Method Wet X Dry

3. Surface Preparation Machined X Rough

4. Equipment Portable Prods Stationary Equipment X Yoke

5. Date Equipment Calibrated 1/3/95

6. Bath Strength 1.2 to 2.4 ML (Visible) 0.1 to 7 ML (fluorescent)

7. Magnetic Field Y Longitudinal Circular

8. Apply Particles X Continuous Residual

9. Determining Amperage for longitudinal 6 AMP AC YOKE

For Circular

10. Product Spacing 2"-8" Acceptance Standard 2"-8"

11. Interpretation NO RECORDABLE INDICATIONS FOUND

12. Accepted 2

Rejected 0

Tested 2

Inspector Richard M. Smith  
Level 1  
Date of Recertification 9/96

TR-1073-AR-008  
ALABAMA SLING CENTER

E20988  
Bridle Sling

### Certificate of Conformance

This is to certify that the wire rope slings/assemblies have been tested and conform to the information contained herein:

Sold to: LAKE SHORE INC.  
MANUFACTURE DIVISION  
IRON MOUNTAIN, MI 49801

M. O. # 04261435

Shipped to: LAKE SHORE INC.  
921 RIVER STREET  
ONTONAGON, MI 49953

Customer Order # 109590

Material Description 6 x 36 XIP IWRC

Customer Part #

Reel Number 38401687 & 02540537

Material broken at N/A pounds.

Sling/Assembly Description (2) WRS-125-HT-HT 2 1/4" x 17'

Sling/Assembly proofloaded to 176,000 pounds in a straight pull.

Any warranty, expressed or implied as to quality, performance, or fitness for use is always premised on the condition that the published rated capacities apply only to new, unused slings and assemblies, that the mechanical

#### WARRANTY

equipment on which such products are used is properly designed and maintained, that such products are properly stored, handled, used, and maintained, and properly inspected on a regular basis during the period of use.

Alabama Sling Center

P.O. Box 203

Dolomite, AL 35061

Signed

Title

GENERAL MANAGER

Date

1/16/95

LSI 03005



# LAKE SHORE INC.

AN OLDENBURG GROUP COMPANY  
IRON MOUNTAIN, MICHIGAN 49801

(906) 774-1500

FAX (906) 774-1505

## PURCHASE ORDER

ORWARD SEPARATE INVOICES IN TRIPLICATE FOR EACH ORDER  
PLEASE MAIL ALL CORRESPONDENCE, AND ACKNOWLEDGEMENT

C: P.O. BOX 809, IRON MOUNTAIN, MICHIGAN 49801

ORDER NUMBER MUST BE SHOWN ON ALL  
SHIPMENTS, SHIPPING PAPERS, INVOICES  
AND CORRESPONDENCE.

P/O NUMBER

PAGE

109590-00

01

P/O DATE

CHANGE/CANCEL

12/20/1994

(Ship to the above address unless specified below.)

ORDERED  
FROM

WIRE ROPE  
609 N. SECOND STREET  
P.O. BOX 288  
ST. JOSEPH, MO 64502

SHIP  
TO

LAKE SHORE INC  
921 RIVER STREET  
ONTONAGON MI 49953

ORDER TYPE	BUYER	ACKNOWLEDGE	CONFIRM	TERMS	F.O.B.	SHIP VIA	COL/PP
NORMAL	JODY BIGALKE	YES	YES	NET 45 DAY	SHIPPING	SEE ATTACHED	COL

LINE NUMBER	QUANTITY ORDERED BLANKET TYPE	U/M	OUR ITEM NUMBER DESCRIPTION/NOTES	YOUR ITEM NUMBER	PRICE/UNIT	REQUESTED DATE	CHANGE/ CANCEL
01	2	EA	E20988 DWG REV: NO SLING, BRIDLE, COMPLETE TO DWG UP RIGGERS & TOOL SUPPLY DWG REV: NO THE FOLLOWING PQR'S ARE INVOKED PER LSI QAF 6.2 DELIVERABLE (DELV) NON-DELIVERABLE (NON-DELV) 118 PRESERV PKG/SHIP (NON-DELV) **JOB ARM042** GOV'T CONTRACT #: DAAK01-93-D-0007 GOV'T PRIORITY RATING: DC-CO SPECIFICATIONS AND STANDARDS. UNLESS OTHERWISE SPECIFIED, THE FOLLOWING SPECIFICATIONS AND STANDARDS OF THE ISSUE LISTED IN THAT ISSUE OF THE DEPARTMENT OF DEFENSE INDEX OF SPECIFICATIONS AND STANDARDS (DODISS) DATED 91JULY01 WITH SUPPLEMENT 01MAY92 AS SPECIFIED IN THE SOLICITATION, FORM A PART OF THIS PURCHASE ORDER TO THE EXTENT SPECIFIED HEREIN.  CONFIRMING TO KATHY ON 12-19-94  BY AUTHORIZED ACKNOWLEDGEMENT OF		2,240.640	01/20/1995	

1-9-95 - Vendor waiting  
for end fitting from  
their supplier. Sub by 1-12  
after receipt - ship 2 days later  
  
1-18  
shipped 1-16 via CF  
will fax auto today

PL ACKNOWLEDGE RECEIPT AND  
AC. NCE OF THIS ORDER BY SIGNING  
AND RETURNING TO US IMMEDIATELY THE  
ATTACHED ACKNOWLEDGEMENT COPY.

SHIPPING INSTRUCTION MUST BE  
FOLLOWED.

3. THIS ORDER REPRESENTS AN OFFER TO  
PURCHASE THE GOODS DESCRIBED HEREIN  
SUBJECT TO THE TERMS AND CONDITIONS ON THIS  
AND THE REVERSE SIDES OF THIS ORDER AND ANY  
ATTACHEMENTS HERETO, AND ACCEPTANCE OF  
THIS ORDER IS LIMITED TO THOSE TERMS AND  
CONDITIONS.

TAX STATUS - LICENSE K38-0740937  
Taxable ..... Not Taxable .....

1. Ind. Processing

2. RES/

Reason ..... 3. Other

PURCHASING

LSI 03006

AUTHORIZED PURCHASING AGENT

(attachment to test  
procedures/reports)

EQUIPMENT MODULAR CAUSEWAY FERRY (MCF)

JOB NUMBER 1073 AR

SERIAL NUMBER HULL # 1

TR-1073-AR-009 SECTION FRUGBOARD

This test report/procedure has been reviewed and is  
properly signed off. All data blanks and tables are  
filled in.

Q.C. INSPECTOR Earl H. Kelle

DATE June 7, 1995

LAKE SHORE INC.  
An Oldenburg Group Company  
KINGSFORD, MICHIGAN

SHEET 1 OF 5  
DATE October 18, 1994  
REVISED May 3, 1995

TP-1073-AR-009  
CDRL A010

MODULAR CAUSEWAY FERRY  
SECTION FREEBOARD  
TEST PROCEDURE

TP-1073-AR-009

CUSTOMER ATCOM

CUSTOMER JOB NO. N/A

CUSTOMER P.O. NO. DAAK01-93-D0007

HULL NOS. First Article

EQUIPMENT Modular Causeway Ferry

EQUIPMENT NO. E03155

EQUIPMENT SERIAL NOS. P40P-0001, P40P-0002 (Powered Modules)

CUSTOMER NOTIFICATION PRIOR TO TESTING 7 DAYS

ENGINEERING NOTIFICATION PRIOR TO TESTING 14 DAYS

LAKE SHORE SALES ORDER NO. 1073AR

DRAWN John C. Lee DATE OCT 18, 1994

CHECKED Rick Symon DATE OCT 18, 1994

APPROVED Walter Heller DATE 10-19-94

QUALITY Kurt Morrison DATE 10/19/94

LSI 03220

LAKE SHORE INC.  
An Oldenburg Group Company  
KINGSFORD, MICHIGAN

SHEET 2 OF 5  
DATE October 18, 1994  
REVISED May 3, 1995

TP-1073-AR-009  
CDRL A010

Rev	Date	Appvl	Q.A.	Description
-	10/21/94	<i>[Signature]</i>	LSI 1 QA	Initial Issue
A	1-26-95	WJK	1 QA	Revised procedure throughout to reflect final test configuration.
B	5/3/95	WJK	<i>K. Vian</i>	Revised procedure to measure freeboard overboard with modules in water. Added second intermediate section. Revised TR-1073-AR-009 to suit.

LSI 03221

TP-1073-AR-009  
CDRL A010

MODULAR CAUSEWAY FERRY  
SECTION FREEBOARD TEST PROCEDURE  
TP-1073-AR-009

1.0 INTRODUCTION

- 1.1 Objective. The objective of the Section Freeboard Test is to verify that each section of the Modular Causeway Ferry (MCF) (Powered Section, Intermediate Section, Beach/Sea End Section) meets the freeboard requirements specified to assure interoperability with MCS and NL Section designs. Testing shall demonstrate that each section of the MCF will have a lightship freeboard of 40  $\pm$  2 inches and a rated load freeboard of not less than 12 inches.
- 1.2 Test Item. The test item, described as the MCF, is defined by Lake Shore drawing E03155 and includes one Powered Section (E19203), two Intermediate Sections (E19193), and one Beach/Sea End Section (E19183).
- 1.3 Test Limitations. Section Freeboard Testing will be performed with the sections in water. To obtain the most accurate freeboard measurements, the water must be dead calm. For water that is other than dead calm, subjective readings to determine the average freeboard will be made.

2.0 REFERENCE DOCUMENTS

- 2.1 PD 1990-0098 Purchase Description (Para's 4.5.2.7.1, 3.5.22.1, 3.5.22.2)
- 2.2 E20001 General Test Requirements
- 2.3 E20011 Failure Reporting, Analysis, and Corrective Action System (FRACAS)

3.0 TEST PREPARATION

- 3.1 Approach to Test. The freeboard of each section of the MCF will be determined by direct measurement at each corner of each section. Freeboard will be determined for both the lightship and fully loaded conditions.
- 3.2 General Test Requirements. Refer to Ref 2.2 and 2.3 general test requirements:
- 3.3 Government Notification. The ATCOM and Government Quality Assurance Representative shall be provided with seven (7) days notification prior to the start of testing.
- 3.4 Personnel Requirements. The following personnel are required for performance of the Section Freeboard Test:
  - 3.4.1 Contractor Furnished Personnel: Test supervisor, Test assistant.
  - 3.4.2 Government Furnished Personnel: Dock side personnel for mooring, fueling, and rigging and handling the MCF load.



TP-1073-AR-009  
CDRL A010

- |       |   | <u>CFE</u> | <u>GFE</u> |
|-------|---|------------|------------|
| 3.5   | <u>Facilities and Test Equipment.</u> The following facilities, support equipment, and test equipment are required for performance of the Section Freeboard Test (CFE = Contractor furnished equipment, GFE = Government/Customer furnished equipment): |            |            |
| 3.5.1 | One (1) complete MCF Powered Section, outfitted for duty, two (2) complete MCF Intermediate Sections, one (1) complete MCF Beach/Sea End Section  |            | X          |
| 3.5.2 | 350 short tons of load with rigging for handling the load.  |            | X          |
| 3.5.3 | Diesel fuel oil, ASTM D975 Grade 2-D or equal, 800 gallons.   |            | X          |
| 3.5.4 | Mooring lines and dockside equipment for mooring the MCF to the pier.   |            | X          |

#### 4.0 TEST PROCEDURE

- 4.1 Section Freeboard Testing will be performed after each section is assembled, and prior to connecting the sections into the 320 foot MCF configuration. Test data shall be recorded on the Test Report TR-1073-AR-009.
- 4.2 For each section, measure and record the freeboard at each corner in the lightship condition.
- 4.3 For each section, measure and record the freeboard at each corner in the full load condition. Full load is defined as 100 short tons of cargo for the Intermediate and Beach/Sea End Sections and 50 short tons of cargo for the Powered Section, and 800 gallons of fuel on board. The load shall be distributed evenly on the deck of the sections.
- 4.4 For each section, calculate the mean freeboard for the lightship and full load conditions.

#### 5.0 ACCEPTANCE CRITERIA

- 5.1 Acceptance criteria is as follows:
  - Lightship condition - Freeboard = 40  $\pm$  2 inches to accept
  - Full load condition - Freeboard = 12 inches minimum to accept

LAKE SHORE INC.  
An Oldenburg Group Company  
KINGSFORD, MICHIGAN

SHEET 5 OF 5  
DATE October 18, 1994  
REVISED May 3, 1995

TR-1073-AR-009  
CDRL A010

MODULAR CAUSEWAY FERRY  
SECTION FREEBOARD TEST

TEST REPORT

TR-1073-AR-009

CUSTOMER ATCOM

CUSTOMER P.O. NO. DAAK01-93-D-0007

EQUIPMENT MODULAR CAUSEWAY FERRY

DATE OF MEASUREMENTS LIGHTSHIP 5/8/95 FULL LOAD 5/11/95 & 5/12/95

LOCATION FORT EUSTIS.

DRAFT MARKS APPLIED PROPERLY Acc ✓ Not Acc       

MEASURED FREEBOARD - LIGHTSHIP							
SECTION	PORT FWD	PORT AFT	STBD FWD	STBD AFT	MEAN (13.1)	ACCEPTABLE	NOT ACCEPTABLE
Powered	33.0	32.0	30.5	29.75	31.31	—	—
Intermediate #1	36.5	37.5	36.5	37.5	37.0		✓
Intermediate #2	36.75	37.38	36.5	37.25	36.97		✓
Beach/Sea	39.75	36.0	40.0	35.75	37.88		✓

MEASURED FREEBOARD - FULL LOAD							
SECTION	PORT FWD	PORT AFT	STBD FWD	STBD AFT	MEAN (13.1)	ACCEPTABLE	NOT ACCEPTABLE
Powered	—	—	—	—	—		
Intermediate #1	14.5	17.0	13.5	15.5	15.13	✓	
Intermediate #2	15.0	13.0	15.0	13.0	14.0	✓	
Beach/Sea	21.0	17.0	19.5	15.0	18.13	✓	

NOTES: Lightship measured on May 8, 1995  
Full Load measured on May 11, 1995 & May 12, 1995  
NO FREEBOARD REQUIREMENTS REQUIRED IN POWERED SECTION.

Test Witnessed by: W. Miller  
LSI Rep W. Miller Customer Rep Donald B. [Signature] Other       

LSI 03224

# FAILURE IDENTIFICATION REPORT

Failure Date MAY 8, 1995

Failure No. TP- 1073-AR-009-FI 01

LSI Job No. \_\_\_\_\_

Customer Contract No. DAAK01-93-00007

	<u>Name</u>	<u>Part No.</u>	<u>Serial No.</u>
Equipment	<u>MODULAR CASSIDAY FAULT</u>		<u>#1</u>
Subassembly	<u>NON POWERED SECTIONS</u>		
Failed Part	<u>FREBOARD</u>		

1. Test Failed / Paragraph:

TP 1073-AR-009 P 5.1

2. Total Test Time at Failure: \_\_\_\_\_ hrs \_\_\_\_\_ cycles

N/A

3. Description of Failure / Symptoms:

Photograph Y (N)

MEASURED MEAN FREBOARD ARE LESS THAN THE 40" - 2" AS REQUIRED FOR LIGHT SHIP CONDITION

4. Other Equipment Failed or Affected:

NONE

5. Repair Action:

NO REPAIR ACTION. MODULE WEIGHTS PER TP AR-1073-002 ARE WITHIN P.D. LIMITS AND ARE SIMILAR TO EXISTING G.F.E. REQUEST WAIVER FOR 38" FREBOARD REQUIREMENT.

Engineering Contact: E. RAMLOW

6. LSI Test Supervisor: W KELLER W

Date JUN 5 1995

Submit to Engineering for Failure Analysis

LSI 03225

SIZE	CODE IDENT. NO.	DRAWING NO.	REV.
A	34712	E20011	A
SCALE	SHEET		3 of 3

(attachment to test  
procedures/reports)

EQUIPMENT MODULAR CAUSEWAY FERRY (MCF)

JOB NUMBER 1073 AR

SERIAL NUMBER HULL # 1

TR-1073-AR-017 EMI/EMC

This test report/procedure has been reviewed and is  
properly signed off. All data blanks and tables are  
filled in.

Q.C. INSPECTOR Carl H. Karlan

DATE June 7, 1995

LAKE SHORE INC.  
An Oldenburg Group Company  
KINGSFORD, MICHIGAN

SHEET 1 OF 7  
DATE October 19, 1994

TP-1073-AR-017  
CDRL A010

**MODULAR CAUSEWAY FERRY  
EMI/EMC TEST  
TEST PROCEDURE**

**TP-1073-AR-017**

CUSTOMER ATCOM

CUSTOMER JOB NO. N/A

CUSTOMER P.O. NO. DAAK01-93-D0007

HULL NOS. First Article

EQUIPMENT Modular Causeway Ferry

EQUIPMENT NO. E03155

EQUIPMENT SERIAL NOS. P40P-0001, P40P-0002 (Powered Modules)

CUSTOMER NOTIFICATION PRIOR TO TESTING 7 DAYS

ENGINEERING NOTIFICATION PRIOR TO TESTING 14 DAYS

LAKE SHORE SALES ORDER NO. 1073AR

DRAWN P J JACOBS DATE OCT 17, 1994

CHECKED Rich Xabo DATE Oct 19, 1994

APPROVED William J Keller DATE OCT 19 1994

QUALITY Keith Mattson DATE 10/19/94

LSI 03163

**LAKE SHORE INC.**  
*An Oldenburg Group Company*  
**KINGSFORD, MICHIGAN**

**SHEET 2 OF 7**  
**DATE October 19, 1994**

TP-1073-AR-017  
CDRL A010

Rev	Date	Appvl	Q.A.	Description
--	10/21/94	WJK	LSI 1 QA	Initial Issue

LSI 03164

TP-1073-AR-017  
CDRL A010

**MODULAR CAUSEWAY FERRY  
EMI/EMC TEST PROCEDURE**

**TP-1073-AR-017**

**1.0 INTRODUCTION**

- 1.1 Objective. This test will demonstrate the absence of Electromagnetic Interference (EMI) aboard MCF, and Electromagnetic Compatibility (EMC) of electrical and electronic systems installed on MCF. EMI/EMC performance of the MCF shall be in accordance with requirements of Purchase Description, Paragraph 3.5.14.
- 1.2 Test Item. The test item, described as the MCF, is defined by Lake Shore drawing E03155.
- 1.3 Test Limitations. Phase I of EMI/EMC Testing will be performed dockside during vehicle offload test. Phase II of the EMI/EMC test will be conducted while underway in a typical operating condition, and will be performed in conjunction with centralized propulsion control and maneuvering trials. Coordination of Phase II testing with other underway testing is the responsibility of the contractor and will be done prior to getting underway.
- 1.4 Special Conditions. Performance of Phase II will require Government authorization to transmit on VHF-FM marine channels, and DOD tactical frequencies.

**2.0 REFERENCE DOCUMENTS**

- |     |              |   |
|-----|--------------|---|
| 2.1 | PD 1990-0098 | Purchase Description (Para's 4.5.2.7.8, 3.5.14)   |
| 2.2 | E20001       | General Test Requirements   |
| 2.3 | E20011       | Failure Reporting, Analysis, and Corrective Action System (FRACAS)                              |
| 2.4 | MIL-STD-1605 | Procedures for Conducting a Shipboard Electromagnetic Interference (EMI) Survey (Surface Ships) |

**3.0 TEST PREPARATION**

- 3.1 Approach to Test. Phase I of the MCF EMI/EMC test will determine if there are any potential sources of EMI in the electrical system. Phase II of the EMI/EMC test will check all MCF electronic and electrical systems in a systematic manner to ensure Electromagnetic Compatibility in all operating conditions.

TP-1073-AR-017  
CDRL A010

3.2 General Test Requirements. Refer to the following documents for general test requirements:

E20001 General Test Requirements; location and schedule of test, calibration requirements, safety requirements, and general test documentation.

E20011 Failure Reporting, Analysis, and Corrective Action System (FRACAS).

3.3 Government Notification. ATCOM and the Government Quality Assurance Representative shall be provided with seven (7) days notification prior to the start of testing.

3.4 Personnel Requirements. The following personnel are required for performance of the EMI/EMC Test:

3.4.1 Contractor personnel: Test supervisor, MCF operators, MCF crew (Phase II), test equipment technicians.

3.4.2 Government personnel: Dock side personnel for mooring, fueling, and rigging and handling the MCF load (Phase II).

3.5 Facilities and Test Equipment: The following facilities, support equipment, and test equipment are required for performance of the EMI/EMC Test (CFE = Contractor furnished equipment, GFE = Government/Customer furnished equipment):

	<u>CFE</u>	<u>GFE</u>
3.5.1 One (1) complete MCF, outfitted for duty.	X	
3.5.2 RF interference measuring equipment (150 Khz to 25 Mhz), Stoddart NM-25T, Stoddart NM-20 (AN/PRM-1) or equivalent with whip and probe antennas.	X	
3.5.3 SINCGARS, AN/VRC-90A, Radio set.		X
3.5.4 Authorization to transmit on VHF-FM marine channels and DOD tactical frequencies.		X

4.0 TEST PROCEDURE

4.1 Test shall be performed in accordance with MIL-STD-1605(SHIPS). Refer to MIL-STD-1605 paragraphs 5.1 through 5.2.7 for detailed requirements.



TP-1073-AR-017  
CDRL A010

- 4.2 Verify Government authorization to transmit on VHF-FM marine channels and DOD tactical frequencies is secured.
- 4.3 During Phase I, preliminary survey, check all electrical equipment in the operator's cab, on the weather deck, and in one power module for emission of EMI at 150 KHz. Any sources of broadband EMI shall be rechecked at 2 MHz. Sources of emissions which exceed the limits of figure 1 of MIL-STD-1605 shall be incorporated in Categories 6 and 7 of the Phase II test as "Active Equipments" as required in paragraph 5.1.2(e)(5) of MIL-STD-1605.
- 4.4 Before starting Phase II testing perform a complete visual check of the vessel topsides including rigging and masts. Inspection shall ensure there are no loose, rusty, or dirty bond strap, ground, or antenna connections. Correct all deficiencies before starting Phase II of test.
- 4.5 During Phase II energize each transmitter in turn and check for adverse effects on other vessel equipment and radio receivers. MCF radios (VHF-FM, Handy-Talky, and SINCGARS (if installed)) are the monitoring receivers during this phase of the test. No VLF, LF, HF, UHF, RADAR, or SONAR equipment is installed on MCF. Therefore, perform Phase II test categories as listed below.

Category	Active Equipment	Monitoring Equipment
3	Transmitters, VHF & above (VHF-FM, Handy talky, & SINCGARS)	Receivers VHF & above (same as transmitters)
6	Miscellaneous active equipment (From Phase I)	Receivers (all radios)
7	All active equipments from above (transmitters and miscellaneous equipment)	All monitor equipment from above, and other vessel systems (steering, main engine, alarms)

- 4.5.1 During Category 7 testing energize the transmitters in different combinations while monitoring all systems for adverse effects. During the conduct of Phase II interference effects shall be recorded and assigned a level of severity as defined below. Interference to contractor furnished equipment of medium and severe levels shall be corrected. Mild interference and interference to Government furnished equipment shall be documented on the test report.

TP-1073-AR-017  
CDRL A010

- 4.5.1.1 Mild Interference, although detectable, does not hamper the detection and interpretation of a desired signal. Mild interference to a control or monitoring system is detectable but does not result in operation of the equipment or system outside of tolerance limits. This level of interference is mainly a background or nuisance type.
- 4.5.1.2 Medium Interference, interferes with the detection and interpretation of a desired signal. This level of interference causes partial breakup or masking of a desired signal with some loss of signal content. Medium interference to a control or monitoring system is a temporary system maloperation, without danger to personnel, vessel, or mission, from which the system recovers without operator intervention.
- 4.5.1.3 Severe Interference, results in complete loss of a desired signal or interference to the extent that desired signal information of message content cannot be interpreted. Severe interference to a control or monitoring system causes undesired system operation from which the system does not recover by itself, or which could result in a hazardous situation for personnel, vessel, or mission.

## 5.0 ACCEPTANCE CRITERIA

- 5.1 The test will be successfully completed when all identified medium and severe sources of EMI have been identified and corrected.

5/8/95

### INTERFERENCES NOTED:

① WHILE OPERATING "SINGARS" RADIO, KEYING OF "ROSS" TRANSMITTER CAUSED NOISE ON PILOT HOUSE "SINGARS" RECEIVER. \*  
(NO EFFECT ON "SINGARS" BEING MONITORED AT STERN OF MCF).  
PROBLEM WAS CORRECTED BY LOOPING WIRE 392A (OUTPUT OF 24-12VDC CONVERTOR FEEDING "ROSS" SET) TWICE THROUGH A FERRITE INDUCTOR IN J-BOX BELOW 24-12VDC CONVERTOR.

\*NOTE - INTERFERENCE WAS NOTED WHEN KEYING ON "LOW" SETTING, CHANNELS 68, 69, 79.

- NO OTHER PROBLEMS ENCOUNTERED. -

LSI 03168

LSI REP - Ken Nelson 5/8/95  
JOHN CURRY - "MET LABS"

LAKE SHORE INC.  
An Oldenburg Group Company  
KINGSFORD, MICHIGAN

SHEET 7 OF 7  
DATE October 19, 1994

TR-1073-AR-017  
CDRL A010

EMI/EMC TEST

TEST REPORT

TR-1073-AR-017

CUSTOMER ATCOM

CUSTOMER P.O. NO. DAAK01-93-D-0007

EQUIPMENT MODULAR CAUSEWAY FERRY

SHOP ORDER N/A

TEST COMPLETION DATE MAY 8, 1995

Location	Item	Reading	Severity Class	Proposed Corrective Action
SENGARS/ ROSS			SEVERE	FERRITE INDUCTOR INST. ON "ROSS" POWER LINE

(Use additional sheets as required)

SEE METLAB REPORT EMI 356 OF 5/12/95 ATTACHED  
Test Witnessed by:

LSI Rep Ken Nelson 5/9/95 Customer Rep Donald H. [Signature] Other \_\_\_\_\_

LSI 03169



Ref. TP-1073-AR-017

## EMI TEST REPORT FOR A

Modular Causeway Ferry  
Model Number E03155  
S/N: P40P-0001 & P40P-0002

MET REPORT EMI356

### PREPARED FOR:

Lake Shore, Inc.  
P.O. Box 809  
Iron Mountain, MI 49801

### PREPARED BY:

MET Laboratories, Inc.  
914 WEST PATAPSCO AVENUE  
BALTIMORE, MARYLAND 21230-3432



## EMI TEST REPORT FOR A

Modular Causeway Ferry  
Model Number E03155  
S/N: P40P-0001 & P40P-0002

MET REPORT EMI356


PREPARED FOR:

Lake Shore, Inc.  
P.O. Box 809  
Iron Mountain, MI 49801

PREPARED BY:


MET Laboratories, Inc.  
914 WEST PATAPSCO AVENUE  
BALTIMORE, MARYLAND 21230-3432

Test Engineer:

  
J. Curry, MET

Witnessed by:

  
William Keller, Lake Shore, Inc.

  
Army Representative



cc: Sandy Perocleschi w/ ENCLOSURES 5/16/95 2 copies  
PO FILE  
Tom Csmarich w/o ENCLOSURE



## Table Of Contents

1.0	Purpose of Test .....	1
2.0	Test Sample .....	1
3.0	Disposition of Test Sample .....	2
4.0	References .....	2
5.0	List of Abbreviations .....	2
6.0	List of Required Tests .....	3
7.0	Modifications to EUT, Standard Limits and Test Frequencies .....	3
8.0	General Test Setup .....	3
9.0	Results .....	5



## 1.0 Purpose of Test

The purpose of this evaluation was verify compliance of the Lake Shore Modular Causeway Ferry, Model Number E03155 (referred to as EUT hereafter) with MIL-STD-1605 (SHIPS) as indicated in Lake Shore, Inc. Purchase Order 109915-00. The evaluation was required as a result of new construction.

## 2.0 Test Sample

The EUT consisted of two power modules, serial numbers P40P-0001 & P40P-0002, and several modular non-powered sections to comprise a test ferry approximately 80 feet long by 20 feet wide. Each power module is comprised basically of one V8 diesel engine, a "thruster" (propulsion device), and associated control electronics. The ferry is equipped with one SINCGARS transceiver, one VHF ship-to-shore VHF transceiver (Ross Model DSL500) and one handheld VHF ship-to-shore VHF transceiver (Motorola Triton). In addition to these known transmitters, the following shipboard electronics were identified as potential interference sources: engine governor, engine rev. limiter switch, thruster synchronizers, 24VDC —> 110VAC inverter (required by synchronizers) and 24VDC —> 12VDC converter (required by stationary VHF ship-to-shore).

The ferry was designed in accordance with the guidelines set forth in MIL-STD-1310. All topside electronics are housed in the pilot house. Power is fed from a battery supply located below-deck. Interconnections between the power modules is accomplished via conduit which runs across the deck of the ship. Visual inspection of the bonding and grounding revealed nothing unusual. All terminations were clean and neat using "typical" electrical connectors.

A copy of NAVSHIPS 0967-266-1010, "Hull Generated Intermodulation Interference Reduction Techniques for Forces Afloat" was not present aboard the ferry; however, as the ferry does not contain 6 or more VHF transmitters, this requirement truly is not applicable. Further, due to the small number of transmitters, multicouplers and RF filters were not necessary. As the ferry does not utilize RADAR, blankers were not required either.



### 3.0 Disposition of Test Sample

All testing performed at:

Fort Eustis  
Fort Eustis Boulevard  
Newport News, VA 25602

### 4.0 References

MIL-STD-1605 (SHIPS)	Procedures for Conducting a Shipboard Electromagnetic Interference (EMI) Survey (Surface Ships)
MIL-STD-1310	Shipboard Bonding, Grounding and Other Techniques for Electromagnetic Compatibility and Safety
MIL-STD-45662A	Calibration System Requirements
Lake Shore, Inc. purchase order 109915-00	

### 5.0 List of Abbreviations

EUT Equipment Under Test  
dB Decibel  
R.E. Radiated Emissions  
V/m Volts per Meter  
Hz Hertz  
dB $\mu$ V Decibel Microvolts  
kHz Kilohertz  
MHz Megahertz  
S/N Serial Number  
STD Standard  
EMI Electromagnetic Interference  
W Watt





## 6.0 List of Required Tests

In accordance with MIL-STD-1605 (SHIPS), testing is to be performed in two phases. Phase I identifies on-board electrical devices which have the potential to interfere with on-board receivers. (All on-board electronics and transmitters are assumed to be potential sources of interference.) Basically, the determination is made by spot-checking the emission levels at 150 kHz. If the emission levels exceed  $50 \mu\text{V/m/5kHz}$ , then the emission levels at 2 MHz should be spot-checked as well. The emission levels at 2 MHz should not exceed  $15 \mu\text{V/m/5kHz}$ . In the event emission levels at both frequencies exceed their respective limits, then the entire 150 kHz - 25 MHz band must be scanned to determine the maximum emission level.

Once equipment with the potential for interference has been identified Phase II testing is conducted. Phase II basically involves operating all permutations of transmitters, electronic equipment, and electrical equipment identified in Phase I as potential interference sources, trying to identify susceptible receiving systems. The actual on-board receivers are electronic systems are used as the monitoring devices. There are no arbitrary emission/susceptibility level limits imposed. A given device is either susceptible, or it is not.

Phase I is performed dock-side; Phase II is conducted with the ship underway. The intent of Phase I tests is merely to minimize the amount of testing required in Phase II by eliminating electrically "quiet" devices from the test matrix.


## 7.0 Modifications to EUT, Standard Limits and Test Frequencies

Due to high ambient levels, Phase I testing could not be (accurately) performed. However, as all electrical systems operate while under way anyway (with the possible exception of the windshield wiper motor), it really did not matter.

## 8.0 General Test Setup

All tests were conducted with Modular Causeway Ferry configured as shown below. The ferry was operated for a period of approximately 2 hours, during which time trials were being conducted. While the ferry was not loaded, this should have no effect on the EMI characteristics. In fact, this probably represents the worst-case scenario, as the ferry's engines may not be capable of achieving maximum rpm under load. For example, if the engines did not achieve full speed, the electronic engine governor would not operate. Further, the alternator will exhibit higher frequency emissions the faster it is turned.

Figure 1. General Test Setup



Notes:

Antennas mounted on top of pilot house -- pilot house approximately 6.5 feet tall  
First yardarm approximately 8 feet from deck

## 9.0 Results

With the ferry underway, the pilot-house gauges and general handling characteristics of the ferry were observed without any transmitters in operation. As aforementioned, all electrical systems are active when the ship is running, so this "test" checked for interference between the electrical systems and the electronic navigation systems. None was observed.



Next, the SINCGARS transceiver was operated to test for inference between it and the on-board electrical and electronic systems. This test was facilitated by use of a second SINCGARS transceiver located as far aft as possible. No interference was observed.

Next, the (fixed) ship-to-shore VHF was operated while checking for interference to the SINCGARS receiver. It was observed that whenever the ship-to-shore was "keyed-up," interference on the SINCGARS occurred, especially upon release of the microphone button. Next, the hand-held VHF ship-to-shore radio, whose main purpose is really for intra-ship communications, was tested but no such interference was observed.

There were three main differences between the hand-held VHF and the fixed VHF:

- (1) The fixed VHF typically operates at 25W, whereas the hand-held is restricted to 5W or less in order to conserve battery power.
- (2) there was only (approximately) 3 feet separating the SINCGARS' HF antenna and the ship-to-shore's VHF antenna.
- (3) The hand-held VHF was battery operated; the fixed VHF operated from ship power.

In order to test whether it was power-related, the transmit level of the fixed VHF was reduced to 1W. The interference was still observable, which led us to believe the problem was the result of the antenna placement. Unfortunately, moving the antennas about or rewiring the power source for the fixed VHF are not something that can be readily accomplished while underway.

This was the only observed interference while underway. Upon returning to port, further testing was conducted to determine the cause of this interference. First, the antenna was moved to location 'A'. (Reference Figure 1.) The interference lessened, but was still quite noticeable. This seemed to support the antenna spacing theory. Next, the antenna was moved to location 'B'. Although the spacing (from the HF antenna) was actually somewhat further, the interference worsened.

Further inspection revealed that the 24VDC => 12VDC converter used to supply power to the fixed VHF was located directly under location 'B'. Suspecting the converter was susceptible to inductive pick-up (because the interference was worse when the microphone button was released), a ferrite bead was installed over the 12 VDC power lead. This wire is designated '392A' on Lake Shore's wiring diagrams. This reduced the interference greatly, but not totally. Another wrap of the power lead was placed through the ferrite bead. The interference was no longer observable. This was tested over a range of VHF channels (low, middle and high) and both power levels.

The antenna was remounted at its original location. Again, no interference was observed.

(attachment to test  
procedures/reports)

EQUIPMENT MODULAR CAUSEWAY FERRY (MCF)

JOB NUMBER 1073 AR

SERIAL NUMBER HULL # 1

TR-1073-AR-018 MCF INTEROPERABILITY

This test report/procedure has been reviewed and is  
properly signed off. All data blanks and tables are  
filled in.

Q.C. INSPECTOR Edw. L. Parker

DATE Jun 7, 1995

WILL KELLER

JUN X 6 1995

NOTES ON

BACK

SHEETS

LAKE SHORE INC.  
An Oldenburg Group Company  
KINGSFORD, MICHIGAN

SHEET 1 OF 7  
DATE October 19, 1994  
REVISED May 3, 1995

TP-1073-AR-018  
CDRL A010

MODULAR CAUSEWAY FERRY  
MCF INTEROPERABILITY  
TEST PROCEDURE

TP-1073-AR-018

CUSTOMER ATCOM  
CUSTOMER JOB NO. N/A  
CUSTOMER P.O. NO. DAAK01-93-D0007  
HULL NOS. First Article  
EQUIPMENT Modular Causeway Ferry  
EQUIPMENT NO. E03155  
EQUIPMENT SERIAL NOS. P40P-0001, P40P-0002 (Powered Modules)  
CUSTOMER NOTIFICATION PRIOR TO TESTING 7 DAYS  
ENGINEERING NOTIFICATION PRIOR TO TESTING 14 DAYS  
LAKE SHORE SALES ORDER NO. 1073AR

DRAWN J.C. Zelle DATE OCT 19, 1994  
CHECKED Pick Shemanchu DATE OCT 19 1994  
APPROVED William J. Keller DATE OCT 19, 1994  
QUALITY Keith Mattson DATE 10/19/94

LSI 03015

LAKE SHORE INC.  
An Oldenburg Group Company  
KINGSFORD, MICHIGAN

SHEET 2 OF 7  
DATE October 19, 1994  
REVISED May 3, 1995

TP-1073-AR-018  
CDRL A010

Rev	Date	Appvl	Q.A.	Description
--	10/21/94			Initial Issue
A	1/30/95	WJK	LSI 1 QA	General editorial revision deleted ref. 2.4 and reference thereto. added joining instructions. Revised TR to allow for recorder initials.
B	4/17/95	WJK	LSI 1 QA	Revised page 8 of 8 per ATCOM comments (3/21/95 letter from Ben Oh)
C	5/3/95	WJK	<i>K. Ulan</i>	Revised throughout to reflect change to dimensional analysis due to lack of availability of N/L Section.

LSI 03016

TP-1073-AR-018  
CDRL A010

**MODULAR CAUSEWAY FERRY  
MCF INTEROPERABILITY TEST PROCEDURE**

**TP-1073-AR-018**

**1.0 INTRODUCTION**

- 1.1 Objective. The objective of the MCF Interoperability Test is to verify that each section of the Modular Causeway Ferry (MCF) (Powered Section, Intermediate Section, Beach/Sea End Section) has the ability to be connected to NL Causeway Sections and existing GFE MCS Sections. Testing shall demonstrate that the Powered Section and the Intermediate Sections of the MCF will connect to an NL Causeway Intermediate Section and an MCS Intermediate Section through the Navy Flexor/Shear Connector System.
- 1.2 Test Item. The test item, described as the MCF, is defined by Lake Shore drawing E03155. For testing, one Powered Section (E19203) and one Intermediate Section (E19193) will be used.
- 1.3 Test Limitations. MCF Interoperability Testing will be performed with the sections in water in an unloaded condition. MCF specifications require that unloaded freeboard be 40  $\pm$  2 inches to accommodate interoperability (PD Para 3.5.22.1). To verify interoperability, NL and MCS Sections provided by the Customer for performance of this test must meet the MCF specifications for unloaded freeboard.

Interoperability of the MCF with NL Causeway Sections will be determined by test. Interoperability of the MCF with MCS Sections will be determined by extension of the Interoperability with the NL Section.

**2.0 REFERENCE DOCUMENTS**

- |     |              |  |
|-----|--------------|--|
| 2.1 | PD 1990-0098 | Purchase Description (Para's 4.5.2.7.9, 3.5.23, 3.5.22.1)          |
| 2.2 | E20001       | General Test Requirements  |
| 2.3 | E20011       | Failure Reporting, Analysis, and Corrective Action System (FRACAS) |
| 2.4 | 6138992      | Flexor System Assembly and Details                                 |
| 2.5 | 6138929      | Pontoon Assembly/Detail Modified P-1                               |

TP-1073-AR-018  
CDRL A010

- |     |         |                                     |
|-----|---------|-------------------------------------|
| 2.6 | 6138928 | Pontoon Assembly/Detail (P-8 M/F)   |
| 2.7 | 6138921 | Causeway Section Powered - Assembly |
| 2.8 | E02783  | MCF Flexor System                   |

### 3.0 TEST PREPARATION

- 3.1 Approach to Test. Interoperability of the MCF with NL Sections will be determined by a dimensional analysis of an MCF Powered Section, Intermediate Section and an NL Intermediate Section end-to-end through the Flexor/Shear Connector System. The analysis will be verified by actual measurements of a LSI Powered Section and a LSI Intermediate Section.

Interoperability of the MCF with MCS Sections will be determined by extension of the Interoperability with the NL Section.

- 3.2 General Test Requirements. Refer ref. 2.2 and 2.3 for general test requirements:
- 3.3 Government Notification. ATCOM and the Government Quality Assurance Representative shall be provided with seven (7) days notification prior to the start of testing.
- 3.4 Personnel Requirements. The following personnel are required for performance of the MCF Interoperability Test:

3.4.1 Contractor furnished personnel: Test supervisor and MCF test crew.

3.4.2 Government furnished personnel: Test witness.

- 3.5 Facilities and Test Equipment. The following facilities, support equipment, and test equipment are required for performance of the MCF Interoperability Test (CFE = Contractor furnished equipment, GFE = Government/Customer furnished equipment):

3.5.1 One (1) complete MCF Powered Section, outfitted for duty and one (1) complete MCF Intermediate Section.

CFE   GFE

X

3.5.2 Mooring lines and dockside equipment for mooring the MCF to the pier.

X

3.5.3 NL Causeway Intermediate Section drawings (Reference 2.4 through 2.7)

X



TP-1073-AR-018  
CDRL A010

#### **4.0 TEST PROCEDURE**

- 4.1 MCF Interoperability Testing will be performed after a section is assembled, and in the water, prior to connecting the sections into the 320 foot MCF configuration. Test data shall be recorded on the Test Report TR-1073-AR-018.
- 4.2 For each section, measure and record the freeboard. (For the MCF Sections, refer to Test Procedure TP-1073-AR-009 and Lake Shore Drawing E19993.)
- 4.3 Perform dimensional analysis using References 2.4 through 2.7 to determine locations of flexor and shear connector centerlines relative to the centerline of the C.S.P.
- 4.4 Verify centerline locations paragraph 4.3 are in agreement with Reference 2.8.
- 4.5 Survey LSI powered and intermediate sections locating transverse centerlines of the sections, pontoons, flexor and shear connectors. Determine as-built dimensions.
- 4.6 Compare dimensions of paragraph 4.5 to Reference 2.8 (see paragraph 4.4).

#### **5.0 ACCEPTANCE CRITERIA**

- 5.1 LSI MCF sections will be shown to dimensionally join to existing GFE N/L and MCS sections.

LAKE SHORE INC.  
An Oldenburg Group Company  
KINGSFORD, MICHIGAN

SHEET 6 OF 7  
DATE October 19, 1994  
REVISED May 3, 1995

TR-1073-AR-018  
CDRL A010

**MODULAR CAUSEWAY FERRY  
INTEROPERABILITY TEST**

**TEST REPORT**

**TR-1073-AR-018**

CUSTOMER ATCOM

CUSTOMER P.O. NO. DAAK01-93-D-0007

EQUIPMENT MODULAR CAUSEWAY FERRY

DATE OF MEASUREMENTS \_\_\_\_\_

LOCATION \_\_\_\_\_

**MCF Interoperability Test Results:**

Unloaded freeboard measurements (Specified at 40  $\pm 2$  inches)

	MCF Powered Section	MCF Intermediate Section	BY
Freeboard			

TR-1073-AR-018  
CDRL A010

Distance From Centerline To:	CSP Dimension	LSI Drawing Dimension - Int. Section	LSI As-Built Dimension - Int. Section	LSI Drawing Dimension - Powered Section	LSI As-Built Dimension - Powered Section	Notes
Center Module Female Connector	18.63	18.63	18.63	18.63	18.63	
Outboard Module <sup>LF</sup> Male Connector	* 85.0	85.50	85.50	85.50	85.75	SEE * BACK OF THIS SHEET.
Outboard Module <sup>LR</sup> Flexor Housing	115.0	115.0	115.0	115.0	115.25	GAP BTWN MODULE ISO'S IS 3/8"
Center Module Male Connector	18.63	18.63	18.63	18.63	18.56	
Outboard Module <sup>RR</sup> Female Connector	85.50	85.50	85.63	85.50	85.88	
Outboard Module <sup>RR</sup> Flexor Housing	115.0	115.0	115.0	115.0	115.25	GAP BTWN MODULE ISO'S IS 3/8"
Flexor Housing to Flexor Housing Dimension	230.0	230.0	230.0	230.0	230.50	EXCESS DUE TO GAP BTWN MODULES
Outboard Male to Outboard Female Connector	171.0	171.0	171.13	171.0	170.63	

**NOTE:**

- (1) All dimensions to transverse centerlines.

SEE COMMENTS ON REVERSE OF THIS SHEET.

Acceptable ☒ Not Acceptable ☐

Test Witnessed by:

LSI Rep Earl W. Rahn Customer Rep Donald R. Brey Other \_\_\_\_\_



8 MAY 95

THE NAVY DWG. 6138921 HAS A DISCREPENCY  
IN AS MUCH AS IF YOU FIGURE THE DIMENSION  
FROM THE OVERALL WIDTH OF 21'-4" WHICH IT IS.  
(SHT. 2 OF 8921 HAS A DIMENSION OF 21'-3" WHICH DOES  
NOT INCLUDE THE THICKNESS OF THE OUTBOARD ANGLES).  
USING 21'-4" WORKING TOWARDS THE SHIP'S CENTERLINE  
IT COMES OUT TO 85.50 FROM SHIP'S CENTERLINE  
TO THE MALE CONNECTOR. IF YOU USE THE DIMENSIONS  
FROM THE CENTERLINE OF THE SHIP OUTWARD THE  
DIMENSION TO THE MALE CONNECTOR COMES OUT TO 85.0.